## **GENERAL NOTES**

TO STA. FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT

## **IDOT STANDARDS**

000001-05 001001-02 001006 442201-03 664001-02 701321-10 701606-06 701901-01 704001-05 BLR22-6

STANDARD SYMBOLS, ABBREVIATIONS & PATTERNS
AREAS OF REINFORCEMENT BARS
DECIMAL OF AN INCH AND OF A FOOT
CLASS C AND D PATCHES
CHAIN LINK FENCE
LANE CLOSURE, 2L, 2W, BRIDGE REPAIR WITH BARRIER
URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN
TRAFFIC CONTROL DEVICES
TEMPORARY CONCRETE BARRIER
TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES FOR CONSTRUCTION ON RURAL LOCAL HIGHWAYS

1.) UTILITY LINES WERE PLOTTED FROM INFORMATION FURNISHED BY THE VARIOUS UTILITY COMPANIES INVOLVED AND THEIR ACCURACY SHOULD BE CONSIDERED APPROXIMATE ONLY.
J.U.LI.E. - JOINT UTILITY LOCATION INFORMATION FOR EXCAVATORS SYSTEM (1-800-892-0123).

2.) RIGHT-OF-WAY LOCATIONS WERE PLOTTED FROM EXISTING PLANS (CIRCA 1983).

- 3.) ENGLISH UNITS OF MEASUREMENT SHALL GOVERN OVER AND SUPERSEDE ANY METRIC UNITS SHOWN IN THIS CONTRACT. WHERE INCLUDED, METRIC UNITS ARE FOR INFORMATION ONLY.
- 4.) ALL ELEVATIONS SHOWN IN THE PLANS ARE BASED ON CITY OF DECATUR DATUM. STATION AND OFFSET CALL OUTS ARE FROM THE CENTERLINE OF SURVEY FOR ALL STREETS.

WHERE NOTED ON PLANS, EXISTING STORM SEWERS SHALL BE REMOVED IN ACCORDANCE WITH SECTION 551 OF THE STANDARD SPECIFICATIONS EXCEPT THAT THE CONTRACTOR WILL NOT BE REQUIRED TO SALVAGE ANY EXISTING SEWER PIPE.

## **SUMMARY OF QUANTITIES**

			TOTAL
PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	IOO% CITY
20800150	TRENCH BACKFILL	CU YD	4
44000100	PAVEMENT REMOVAL	SQ YD	14
44201341	CLASS C PATCHES, TYPE II, 9"	SQ YD	32
50102400	CONCRETE REMOVAL	CU YD	106
50300225	CONCRETE STRUCTURES	CU YD	129.2
50300255	CONCRETE SUPERSTRUCTURE	CU YD	10.6
50300260	BRIDGE DECK GROOVING	SQ YD	27
50300280	CONCRETE ENCASEMENT	CU YD	2.2
50300300	PROTECTIVE COAT	SQ YD	33
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1
50500505	STUD SHEAR CONNECTORS	EACH	224
50600300	CLEANING AND PAINTING STEEL BRIDGE	L SUM	1
50606400	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES	L SUM	1
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	21550
50800515	BAR SPLICERS	EACH	108
52000365	NEOPRENE EXPANSION JOINT, 6 1/2"	FOOT	96
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	28
52100520	ANCHOR BOLTS, 1"	EACH	112
54248510	CONCRETE COLLAR	CU YD	1.2

*	SPECIALTY	TTEM



PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY IOO% CITY
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	12
55100500	STORM SEWER REMOVAL 12"	FOOT	12
58700300	CONCRETE SEALER	SQ FT	652
59000200	EPOXY CRACK INJECTION	FOOT	253
66411900	TEMPORARY FENCE	FOOT	478
67100100	MOBILIZATION	L SUM	1
70106800	CHANGEABLE MESSAGE SIGN	CA MO	8
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	11
Z0018800	DRAINAGE SYSTEM	L SUM	1
Z0031200	JACKING AND CRIBBING	EACH	8
X0320887	POLYMER CONCRETE	CU FT	16
X0321963	MICRO-PILES	EACH	4
X0323432	MICROPILE LOAD TEST	EACH	2
X0323433	MICROPILE PROOF LOAD TEST	EACH	4
X0323830	DRAINAGE SCUPPERS, DS-11	EACH	4
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	126
X7010010	TRAFFIC CONTROL - STAGE I	L SUM	1
X7010020	TRAFFIC CONTROL - STAGE II	L SUM	1