

| CONTRACT NO. 95585 | F.A.U | SECTION | COUNTY | TOTAL | SHEET | NO. 7369 | 08-00503-00-BR | MACON | 24 | 24 | STA. | TO STA. | EED | COUNTY | TO


FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT



<u>ELEVATION</u>



SECTION A-A



<u>U BAR</u>

REINFORCED CONCRETE PIPE EXTENSION COLLAR SCHEDULE*									
PIPE DIAMETER	S BARS		U BARS DIMENSIONS					REINFORCING BARS	CONCRETE COLLAR
		LENGTH (INCHES)	NUMBER BARS	A (INCHES)	B (INCHES)	LAP (INCHES)	A+2B LENGTH (INCHES)	POUND	CU YD
12"	12	20	6	23	19	15	61	34	0.3

\* THE COST OF CONCRETE COLLAR IS TO BE INCLUDED IN THE COST OF REMOVING INLETS TO MAINTAIN FLOW.

