| SUMMARY OF QUANTITIES - BASE BID | | | | | | |
|----------------------------------|----------------------------------|------|---------------------|------------------------|--|--|
| ITEM NO. | DESCRIPTION | UNIT | TOTAL QUANTITIES | as Built Quantities | | |
| AR150510 | ENGINEER'S FIELD OFFICE | L.S. | 1 | | | |
| AR150530 | TRAFFIC MAINTENANCE | LS. | 1 | | | |
| AR150540 | HAUL ROUTE | LS. | 1 | | | |
| AR152540 | SOIL STABILIZATION FABRIC | S.Y. | 7,094 | | | |
| AR156510 | SILT FENCE | L.F. | 1,148 | | | |
| AR156531 | EROSION CONTROL BLANKET | S.Y. | 984 | | | |
| AR201900 | REMOVE BITUMINOUS PAVEMENT | S.Y. | 5,027 | | | |
| AR501900 | REMOVE PCC PAVEMENT | S.Y. | 170 | | | |
| AR510510 | TIE DOWN | EACH | 9 | | | |
| AR620520 | PAVEMENT MARKINGWATERBORNE | S.F. | 137 | | | |
| AR620525 | PAVEMENT MARKING-BLACK BORDER | S.F. | 125 | | | |
| AR701215 | 15" CMP | L.F. | 153 | | | |
| AR701515 | 15" RCP, CLASS IV | L.F. | 107 | | | |
| AR751051 | SLOTTED DRAIN | L.F. | 200 | | | |
| AR751600 | CATCH BASIN | EACH | 1 | | | |
| AR752415 | PRECAST REINFORCED CONC. FES 15" | EACH | 1 | | | |
| AR901510 | SEEDING | ACRE | 1 | | | |
| AR908510 | MULCHING | ACRE | 1 | | | |

| SUMMARY OF QUANTITIES - ALTERNATE BID A | | | | | |
|-----------------------------------------|-------------------------------|------|---------------------|------------------------|--|
| ITEM NO. | DESCRIPTION | UNIT | TOTAL QUANTITIES | AS BUILT QUANTITIES | |
| AS152410 | UNCLASSIFIED EXCAVATION | C.Y. | 1,774 | | |
| AS209510 | CRUSHED AGGREGATE BASE COURSE | TON | 1,632 | | |
| AS501506 | 6" PCC PAVEMENT | S.Y. | 7,026 | | |
| AS501530 | PCC TEST BATCH | EACH | 1 | T | |

| SUMMARY OF QUANTITIES - ALTERNATE BID B | | | | | | |
|-----------------------------------------|-------------------------------|------|---------------------|------------------------|--|--|
| ITEM NO. | DESCRIPTION | UNIT | TOTAL QUANTITIES | as Built Quantities | | |
| AT152410 | UNCLASSIFIED EXCAVATION | C.Y. | 2,191 |] | | |
| AT201610 | BITUMINOUS BASE COURSE | TON | 1,058 | | | |
| AT209510 | CRUSHED AGGREGATE BASE COURSE | TON | 3,235 | | | |
| AT401610 | BITUMINOUS SURFACE COURSE | TON | 632 | | | |
| AT401655 | BUTT JOINT CONSTRUCTION | S.Y. | 100 | | | |
| AT602510 | BITUMINOUS PRIME COAT | GAL. | 2,469 | | | |
| AT603510 | BITUMINOUS TACK COAT | GAL. | 351 | | | |

| | ED016 | B ³ ⁄ |
|-------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| | INDEX TO SHEETS | REVISION B |
| SHEET NO. | DESCRIPTION | DATE |
| 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 | COVER SHEET SUMMARY OF QUANTITIES AND INDEX TO SHEETS PROPOSED SAFETY PLAN EXISTING SITE PLAN PROPOSED PAVEMENT PREPARATION PLAN PROPOSED CONSTRUCTION PLAN PROPOSED TYPICAL SECTIONS PROPOSED CONCRETE REMOVAL DETAILS AND NOTES PROPOSED PLAN AND PROFILE - WEST ALIGNMENT PROPOSED PLAN AND PROFILE - CENTER ALIGNMENT PROPOSED PLAN AND PROFILE - EAST ALIGNMENT PROPOSED PAVEMENT MARKING AND AIRCRAFT TIEDOWN PLAN PROPOSED JOINT CONSTRUCTION AND SEALING DETAILS PROPOSED STORMWATER POLLUTION PREVENTION PLAN PROPOSED CROSS SECTIONS - WEST ALIGNMENT STA. 10+00 TO STA. 13+99 PROPOSED CROSS SECTIONS - CENTER ALIGNMENT STA. 10+00 TO STA. 13+99 | R COUNTY AIRPORT ARIS, ILLINOIS AIP. PROJ.: 3-17-0077-811 |
| 18 | PROPOSED CROSS SECTIONS — EAST ALIGNMENT STA. 10+00 TO STA. 13+70 | HE Project No. OBA0209 0800 Filename R-002FLP_DWG Scole N/A EDGAF Date |
| | | Corguight Harsen Professional Services Inc. 2009 Harson Professional Services Inc. 1525 South Servic Street Springfield, Illinous 627703-2886 www.harson-inc.com Offices Nationwide |
| | | REMOVE AND RECONSTRUCT T-HANGAR TAXIWAYS SUMMARY OF QUANTITIES AND INDEX TO SHEETS |
| | | 2 |

: 15, 2009 10:08 AM COUGHO1079