

MAY 12, 2009 8:37 AM KINGA00394  
 I:\AIRPORTS\SLA-CARBONDALE\08A0067\CADD\AIRPORT\sheet\R-002ELP.DWG - Layout1

SO078


SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	AS BUILT QUANTITIES
AR125961	RELOCATE STAKE MOUNTED LIGHT	EACH	1	
AR125964	RELOCATE TAXI GUIDANCE SIGN	EACH	2	
AR150530	TRAFFIC MAINTENANCE	L.S.	1	
AR201661	CLEAN AND SEAL BITUMINOUS CRACKS	L.F.	5,000	
AR401003	BITUMINOUS SURFACE COURSE METHOD 1, SUPERPAVE	TON	2,050	
AR401650	BITUMINOUS PAVEMENT MILLING	S.Y.	23,800	
AR401915	REM & REPL. BIT. PAVEMENT - TYPE A	S.Y.	850	
AR401916	REM & REPL. BIT. PAVEMENT - TYPE B	S.Y.	440	
AR603510	BITUMINOUS TACK COAT	GAL.	3,600	
AR620520	PAVEMENT MARKING-WATERBORNE	S.F.	37,766	
AR620525	PAVEMENT MARKING-BLACK BORDER	S.F.	43,371	

INDEX TO SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	SUMMARY OF QUANTITIES AND INDEX TO SHEETS
3	PROPOSED SAFETY PLAN
4	PROPOSED CONSTRUCTION SEQUENCING PLAN
5	PROPOSED TYPICAL SECTIONS
6	PROPOSED CONSTRUCTION PLAN STA. 0+00 TO STA. 20+00
7	PROPOSED CONSTRUCTION PLAN STA. 20+00 TO STA. 27+00
8	PROPOSED PAVEMENT PREPARATION PLAN STA. 0+00 TO STA. 20+00
9	PROPOSED PAVEMENT PREPARATION PLAN STA. 20+00 TO STA. 27+00
10	PROPOSED MARKING PLAN
11	PROPOSED MARKING PLAN
12	PROPOSED MARKING PLAN
13	PROPOSED MARKING PLAN
14	PROPOSED MARKING PLAN
15	PROPOSED MARKING PLAN
16	PROPOSED MARKING PLAN
17	PROPOSED MARKING PLAN
18	PROPOSED MARKING PLAN
19	PROPOSED MARKING PLAN
20	PROPOSED SURFACE PAINTED HOLDING POSITION MARKING SIGN DETAILS
21	PROPOSED SURFACE PAINTED HOLDING POSITION MARKING SIGN DETAILS
22	PROPOSED SURFACE PAINTED HOLDING POSITION MARKING SIGN DETAILS
23	TAXIWAY SIGN & LIGHT RELOCATIONS
24	ELECTRICAL DETAILS SHEET 1
25	ELECTRICAL DETAILS SHEET 2
26	ELECTRICAL NOTES SHEET 1
27	ELECTRICAL NOTES SHEET 2

DATE	REVISION	BY

**SOUTHERN ILLINOIS AIRPORT**  
 MURPHYSBORO / CARBONDALE, ILLINOIS  
  
 ILL. PROJ.: MDH-3692      A.I.P. PROJ.: 3-17-0009-B29

Hanson Project No. 08A0067D_0800	04/03/09
Filename R-002ELP.DWG	01/26/09
Scale NOT TO SCALE	04/10/09
Date 01/26/09	
LAYOUT USL	
DRAWN BAK	
REVIEWED CAH	

  
**HANSON**  
 Hanson Professional Services Inc.  
 1800 South 10th Street  
 Springfield, Illinois 62703-2886  
 Offices Nationwide

REHABILITATE  
 TAXIWAY "B"  
 SUMMARY OF QUANTITIES  
 AND  
 INDEX TO SHEETS