

May 29, 2020

SUBJECT: FAI Route 74 (I-74) Project NHPP-PNT4(836) Section 72-[3RS-3;4RS-2;(4HB-2)BJR] Peoria County Contract No. 68A83 Item No. 45, June 12, 2020 Letting Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised the Schedule of Prices
- 2. Revised page 48 of the Special Provisions.
- 3. Revised sheets 10, 11, and 119A of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

Jack A. Elston, P.E. Bureau Chief, Design and Environment

The Office of Planning and Programming Data Management Lab **MUST** be contacted two (2) weeks prior to ANY work being done to ensure proper site selection and post placement. If this is not done any instillation discrepancies determined by the Office of Planning and Programming Data Management Lab must be rectified prior to the equipment installation.

A 4" thick layer of hot-mix asphalt shall be placed from the edge of the shoulders to the location of the concrete foundation (10'–0" wide) to each foundation as directed by the Engineer. The finished grade of the hot-mix asphalt must be no higher than the edge of shoulder elevation and shall follow the existing side slopes. This will be paid at the unit price per Ton for INCIDENTAL HOT-MIX ASPHALT SURFACING.

Full manufacturer's specifications of the components to be furnished under this item shall be approved in writing prior to ordering of components. Warranty information shall be provided to the Engineer at the time of delivery of components.

Contact Information for the Office of Planning and Programming Data Management Lab:

Mr. Rich Marx 126 East Ash Street Springfield, Illinois Phone: (217) 782-2065 Richard.marx@illinois.gov

Furnishing of the components necessary to complete the TRAFFIC COUNTER – TIRTL system will be paid for at the contract unit price each for TRAFFIC COUNTER – TIRTL SYSTEM and shall include all components necessary to complete each installation as herein specified.

Revised May 29, 2020