

Mobile Barriers LLC 24918 Genesee Trail Rd, Golden, CO 80401

BUILD SHEET – Mobile Barriers MBT-1 (new builds)

Our #:MB-1900517Date:May 17, 2019For:Illinois Department of Transportation ("Purchaser") c/o: Chad Sanders, IDOT Bridge Inspection Specialist (Rep: not	one/direct ("Rep"))
This Build Sheet is for Mobile Barriers MBT-1, and subject to the Provision	s below:
<u>MBT-1</u>	Qty
Platforms (bi-directional w/ ballast boxe & misc hardware)	2
Caboose (std fixed axles w/ SBS brakes, air susp, batteriers & TMA plate)	1
Wall Sections (0-3 can be used): 20'	1
10' *	0
* Optional base & outrigger for cranes rated to 301/8600 lbs #	0
Paint & Finish (Whelen LED lighting, misc finish & hardware)	1
Additional Options	
Onboard Pwr (4 GFCI circuits: 2 ea/240/120- Generator not included)	1
Work Lights (FRC 240V/35,000 lumens/6.25A draw)	4
Tool Box (multi-drawer built in)	1
TMA QD (self leveling w/ 2 pin release)	1
TMA Frame Extension (w/ brackets for signage & lift assembly)	1
Matrix Bd (Wanco 4x8' LED on lift w/ solar, radar & programable touch panel)	0
Arrow Bd (Wandco 4x8' LED on lift w/ solar panels & dial controls)	1
Super Singles Only - on Alum Rims (upgrade for extra clearance on fixed axle	<i>es)</i> 1
Crane (Tiger Cranes 8059 30'/8600 lbs plumbed w/ pwr, hook and bucket) #	0
Rear Steer (w/ super singles and wireless controls)	0
TMA TL-3 (Traffix Scorpion C w/ special Heavy Duty-MB pkg & wireless controls)	1
Total (FOB Plant/SD with Payment)	
Overhead & Delivery (w/in USA lower 48 States)	
Special Features & Requirements (itemize in and attach as Schedule A, if any)	
Total Delivered - subject to Provisions below	1

Total Delivered - subject to Provisions below

Color – MB Safety Yellow ALLOW APPROX 12-16 WKS FOR DELIVERY

(Schedule subject to prior commitments and receipt of applicable components)

AGREED & ORDERED this	_ day of	, 20

For Purchaser:

By:_____

Print: ______

Accepted & Agreed for Mobile Barriers LLC by: ______ date: _____