

F.A.D. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
349	16RS-6	WILL	21	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL QUANTITIES	URBAN	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	1000						
20201006	GRADING AND SHAPING SHOULDERS	UNIT	195	195					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	13	13					
40600300	AGGREGATE (PRIME COAT)	TON	65	65					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	10	10					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	107	107					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	891	891					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2709	2709					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	32247	32247					
44002235	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 8 3/4"	SO YD	1445	1445					
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SO YD	420	420					
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SO YD	624	624					
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SO YD	359	359					
48101200	AGGREGATE SHOULDERS, TYPE B	TON	634	634					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3					
67100100	MOBILIZATION	L SUM	1	1					
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1					
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1					
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5124	5124					

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL QUANTITIES	URBAN	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	1000						
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	41000	41000					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	658	658					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	192	192					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	126	126					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	300	300					
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	113	113					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	41000	41000					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	658	658					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	192	192					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	126	126					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	243	243					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	243	243					
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	519	519					
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	52	52					
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1355	1355					

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 U.S. RTE. 30
 (U.S. RTE. 34 TO WILL COUNTY LINE)

4/3/2008 9:50:00 AM C:\p059811_rvw.dgn