	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
					PEORIA	KNOX	TAZEWELL
					100% STATE	100% STATE	100% STATE
					0040	0040	0040
	73302210	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE III-C-A (36" X 7'-0")	FOOT	32.5		32.5	
	73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	217.9	124.6	7.7	85.6
	73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	11	6		5
	73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	3	2	1	
	73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	47	26	1	20
*	X0324181	DISCONNECT SIGN LIGHTING AND REMOVE WIRING TO NEAREST SPLICE	EACH	2	1		1
	X5210005	TIGHTEN SUPPORT ANCHOR BOLT	EACH	25	25		
	X7200075	REMOVE AND REINSTALL SIGN PANEL	SQ FT	560			560
	X7200085	REPLACE AND TIGHTEN SIGN MOUNTING CLIPS PER EACH SIGN	EACH	22	10	8	4
	X7330066	REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	6		6	
	X7330068	TIGHTEN CANTILEVER CONNECTION	EACH	1		1	
	X7330090	METAL SCREEN	EACH	7	2	1	4
	X8140232	REPLACE HANDHOLE COVER BOLT	EACH	8	4	4	
	X8140234	REPLACE HANDHOLE COVER	EACH	2	1	1	

14

* SPECIALITY ITEM

FILE NAME = overhead sign plans.dgn	USER NAME = devisse	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 393.7008 / in.	CHECKED -	REVISED -
	PLOT DATE = 3/21/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
CONTRACT NO. 46314

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	D4-4 OVD SIN STR REPL 14-47	VAR	65	3
		CONTRACT NO. 46314		
	ILLINOIS FED. AID PROJECT			