

Location No.	4-25		
Structure No.	4S0901074R095.50		
County / Route	TAZEWELL I 74		
Scope of work			
Paycode	Payitem	Unit	Quantity
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	1
X7330090	METAL SCREEN	EACH	2
Z0052394	REPLACE U-BOLT	EACH	48
X7200085	REPLACE AND TIGHTEN SIGN MOUNTING CLIPS PER EACH SIGN	EACH	1

Location No.	4-26		
Structure No.	4S0901074R098.30		
County / Route	TAZEWELL I 74		
Scope of work			
Paycode	Payitem	Unit	Quantity
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	1
73300200	OVERHEAD SIGN STRUCTURE - SPAN, TYPE II-A (4'-6" X 5'-3")	FOOT	84
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	20.4
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	1
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	100
72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	324.5
72000300	SIGN PANEL TYPE 3	SQ FT	318.5
73301810	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	25
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	4

Location No.	4-29		
Structure No.	4S0901474R012.20		
County / Route	TAZEWELL I 474		
Scope of work			
Paycode	Payitem	Unit	Quantity
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	1
73300100	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (4'-0" X 4'-6")	FOOT	68
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	12
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	1
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	150
72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	426.5
72000300	SIGN PANEL TYPE 3	SQ FT	372.75
73301810	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	34
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	4