

- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN () WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL 2 SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

	FILE NAME =	USER NAME = pyrzanowskirb	DESIGNED -	REVISED - R. MIRS 09-15-97			ARTERIAL ROA	۸n		F.A.P.	SECTION	COUNTY	TOTAL S	EET
	c:\pw_work\pwidot\pyrzanowskirb\d0355621	D134213-sht-plan.dgn	DRAWN -	REVISED - R. MIRS 12-11-97	STATE OF ILLINOIS					338	110V-R-1-BR	соок	28	27
	PLOT SCALE = 100.0000 ' / in. PLOT DATE = 3/12/2014		CHECKED -	REVISED - T. RAMMACHER 02-02-99	DELYMINICIAL OF THEMSEL	INFORMATION SIGN				555	TC-22	CONTRACT NO. 60W59		59
			DATE -	REVISED - C. JUCIUS 01-31-07		SCALE: NONE	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	FED. ROAL		D. AID PROJECT	,01 00,	