

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0021					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0021					
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	50 YD	9925	9925					70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	22923	22923					
44004250	PAVED SHOULDER REMOVAL	50 YD	2497	2497					*78200410	GUARDRAIL MARKERS, TYPE A	EACH	43	43					
48101200	AGGREGATE SHOULDERS, TYPE B	TON	368	368					*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	10	10					
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	50 YD	10030	10030					X2020110	GRADING AND SHAPING SHOULDERS	UNIT	92	92					
*63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	3388	3388					X4406030	PARTIAL DEPTH REMOVAL, TYPE 1, 3"	50 YD	4991	4991					
*63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	10	10					X4421000	PARTIAL DEPTH PATCHING	TON	839	839					
*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	10	10					X4810200	AGGREGATE SHOULDER REMOVAL	CU YD	1858	1858					
63200310	GUARDRAIL REMOVAL	FOOT	3388	3388					*X7800815	HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE - 4 INCH	FOOT	4692	4692					
64200108	SHOULDER RUMBLE STRIPS, 8 INCH	FOOT	22209	22209					Z0030850	TEMPORARY INFORMATION SIGNING	50 FT	51.4	51.4					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3					Z0055400	RUMBLE STRIP	FOOT	11484	11484					
67100100	MOBILIZATION	L SUM	1	1														
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1														
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1														

URBAN
90% FED.
10% STATE

URBAN
90% FED.
10% STATE

* SPECIALTY ITEMS
 NON-PARTICIPATING ITEMS

FILE NAME: *	USER NAME: * stredso	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
C:\sw\work\p1\p1\stredso\p1\0215\100-0481-01\0215-01.dwg		DRAWN -	REVISED -					SCALE: 1"=100'	SHEET NO. OF SHEETS	STA. TO STA.	557	2013-0481	KANE	24	3	
		CHECKED -	REVISED -					DATE: 5/24/2014								CONTRACT NO. 60X02
		DATE	REVISED													FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT