		TOTALS:			1859		1293
	York Road	EB	2	12	6	72	8
	V - d - D 1	EB	2	12	15	180	20
		EB	2	12	6	72	8
		EB	2	12	30	360	40
		EB	2	12	30	360	40
		EB	2	12	50	600	67
		EB	2	12	6	72	8
		EB	2	12	6	72	8
		EB	2	12	6	72	8
		EB	2	12	6	72	8
		EB	2	12	6	72	8
Church Road		EB	1	3	50	150	17
	Church Road	EB	2	12	12	144	16
		EB	2	12	30	360	40
		EB	2	12	12	144	16
		EB	2	12	12	144	16
		EB	2	12	12	144	16
		EB	2	12	12	144	16
		EB	2	12	6	72	8
		EB	2	12	6	72	8
		EB	2	12	6	72	8
		EB	2	12	6	72	8
		EB	2	12	6	72	8
		EB	2	12	12	144	16
		EB	1	3	200	600	67
Opiace / Wellae		EB	1	12	6	72	8
Spruce Avenue	Opiace Avenue	EB	2	12	6	72	8
	Spruce Avenue	EB	1	3	50	150	17
		EB	2	12	6	72	8
		EB	2	12	6	72	8
		EB	2	12	6	72	8
		EB	2	12	6	72	8 8
Wood Dale Road		EB	2	3 12		450 72	50
Mood Dolo Dood	Wood Dale Road	EB EB	1	12	6 150	72	8
	Mood Dala Daari	EB	2	3	50	150	17
		EB	2	12	6	72	8
		EB	2	12	6	72	8
		EB	1	3	50	150	17
		EB	2	12	6	72	8
		EB	2	12	6	72	8
		EB	2	12	6	72	8
Addison Road		EB	1	3	50	150	17
		(NB/SB)	(1, 2, 3)	WDTH	LENGTH	(SQ FT)	(SQ YE
FROM	ТО	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
	STREET	DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAI

ROUTE:	IL 19 (IL 53 to Sycamore A	ve.)					
00000	OTDEET	DIDECTION		DAY CHELLE		DEDAID	DED.41D
	STREET	DIRECTION	LANE	PAVEMENT	PAVEMENT		REPAIR
FROM	ТО	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
		(NB/SB)	(1, 2, 3)	WDTH	LENGTH	(SQ FT)	(SQ YD)
IL 53		WB	2	12	12	144	16
		WB	1	3	200	600	67
		WB	1	12	50	600	67
		WB	1	3	300	900	100
		WB	1	12	12	144	16
	Medinah Road	WB	1	3	200	600	67
Medinah Road	Sycamore Avenue	WB	1	3	200	600	67
Sycamore Avenue		EB	1	12	6	72	8
		EB	1	3	100	300	33
	Medinah Road	EB	1	3	150	450	50
Medinah Road		EB	1	3	500	1500	167
		EB	1	3	50	150	17
	IL 53	EB	1	5	100	500	56
		TOTALS:			1880		729
					FT		SY

ROUTE	IL 53 (Pleasant Lane to Sic	dney Avenue)					
CROSS	STREET	DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	ТО	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
		(NB/SB)	(1, 2, 3)	WDTH	LENGTH	(SQ FT)	(SQ YD
Pleasant Lane		NB	1	12	6	72	8
	Sidney Avenue	NB	1	12	12	144	16
Sidney Avenue	IL 64	SB	1	12	6	72	8
IL 64		SB	2	12	6	72	8
	Pleasant Lane	SB	1	12	6	72	8
		TOTALS:			36		48
					FT		SY

ILE NAME = USER NAME = Aumm		DESIGNED -	REVISED -
c:\pw_work\pwidot\aumm\d0382486\HMA-DuFage.dgn [DRAWN -	REVISED -
	PLOT SCALE = 100.0000 '/ in.	CHECKED -	REVISED -
Default	PLOT DATE = 4/3/2014	DATE -	REVISED -

STATE OF ILLINOIS							
DEPARTMENT	OF	TRANSPORTATION					

	INTERMITTENT RESURFACING SCHEDULE IL 19 AND IL 53						F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
							VAR.	2014-023RS	DUPAGE	22	11
									CONTRACT	NO. 6	50Y09
	SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT				