INDEX OF SHEETS

STATE STANDARDS

SHEET NO.	DESCRIPTION	STANDARD NO.	DESCRIPTION				
1	TITLE SHEET	000001-06	TYPICAL SYMBOLS, ABBREVIATIONS AND PATTERNS				
2	INDEX OF SHEETS, STATE STANDARDS AND GENERAL NOTES	701011 - 04	OFF-RD MOVING OPERATIONS, 2L, 2W, DAY ONLY				
3	SUMMARY OF QUANTITIES	701301-04	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS				
4	GENERAL LOCATION MAP	701306 <i>~03</i>	LANE CLOSURE, 2L, 2W, SLOW MOVING OPERATIONS - DAY ONLY				
5	ROUTE INFORMATION	701311 - <i>03</i>	LANE CLOSURE 2L. 2W MOVING OPERATIONS - DAY ONLY				
6	SUMMARY OF INTERMITTENT RESURFACING SCHEDULE	•	LANE CLOSURE, 2L, 2W, WORK AREAS IN SERIES				
7-42	INTERMITTENT RESURFACING SCHEDULE						
43	BUTT JOINT AND HMA TAPER DETAILS (80-32)	701421- 06	LANE CLOSURE, MULTILANE, DAY OPERATIONS ONLY, FOR SPEEDS > 45 MPH TO 55 MPH				
44	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS AND DRIVEWAYS (TC-10)	701426 - 06	LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPERATIONS, FOR SPEEDS \geq 45 MPH				
45	TYPICAL APPLICATIONS: RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT) (TC-11)	701427-02	LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPER., FOR SPEEDS $\underline{\zeta}$ 40 MPH				
46	DISTRICT ONE TYPICAL PAVEMENT MARKINGS (TC-13)	701501-06	URBAN LANE CLOSURE, 2L. 2W. UNDIVIDED				
47 48	TRAFFIC CONTROL AND PROTECTION OF TURN BAYS (TO REMAIN OPEN TO TRAFFIC) (TC-14) PAVEMENT MARKING LETTERS AND SYMBOLS FOR TRAFFIC	701502- <i>0</i> 6	URBAN LANE CLOSURE, ZL. 2W. WITH BIDIRECTIONAL LEFT TURN LANE				
49	STAGING (TC-16) ARTERIAL ROAD INFORMATION SIGN (TC-22)	701601 - 09	URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NONTRAVERSABLE MEDIAN				
50	STANDARD TRAFFIC SIGNAL DESIGN DETAILS (TS-05, SHEET 2 OF 7)	701602-07	URBAN_LANE CLOSURE, MULTILANE, 2W WITH BIDIRECTIONAL				
51	DETECTOR LOOP INSTALLATION DETAIL FOR ROADWAY RESURFACING		LEFT TURN LANE				
	(TS-07)	701606 -09	URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN				
		701701 - 09	URBAN LANE CLOSURE, MULTILANE INTERSECTION				
		701901 -03	TRAFFIC CONTROL DEVICES				

HOT-MIX ASPHALT MIXTURE RE	QUALITY MANAGEMENT					
MIXTURE TYPE	AIR VOIDS (%) @ N _{DES.}	PROGRAM (QMP)				
HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70 (IL 9.5MM), 2"	4% @ 70 GYR	QC/QA				
OMP DESIGNATION: QUALITY CONTROL/QUALITY ASSURANCE (QC/QA)						

THE UNIT WEIGHT USED TO CALCULATE ALL HMA SURFACE MIXTURE QUANTITIES IS 112 LBS/50 YD/IN.

THE "AC TYPE" FOR POLYMERIZED HMA MIXES SHALL BE "SBS/SBR PG 76-22" AND FOR NON-POLYMERIZED HMA THE "AC TYPE" SHALL BE "PG 64-22" UNLESS MODIFIED BY DISTRICT ONE SPECIAL PROVISIONS. FOR USE OF RECYCLED MATERIALS SEE SPECIAL PROVISIONS. OUALITY MANAGEMENT PROGRAM (OMP) IDENTIFIES THE PARTICULAR OUALITY CONTROL SPECIFICATION THAT APPLIES TO THE HMA MIXTURE

GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT (800) 892-0123 OR 811 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS FACILITIES.

(48 HOUR NOTIFICATION REQUIRED)

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE (OR TOLLWAY) PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT (OR ISTHA)

ANY PAVEMENT MARKINGS AND RAISED REFLECTIVE PAVEMENT MARKERS OBLITERATED BY MILLING AND RESURFACING OPERATIONS ON SIDE STREETS AND ENTRANCES SHALL BE REPLACED AND PAID FOR IN KIND.

BEFORE BEGINNING ANY WORK, THE CONTRACTOR SHALL RETAIN AND RECORD FOR FUTURE REFERENCE, ALL EXISTING PAVEMENT MARKING LINES (AND RAISED REFLECTIVE PAVEMENT MARKERS) IN ORDER THAT THESE LOCATIONS CAN BE RE-ESTABLISHED FOR STRIPING. EXACT LOCATIONS OF ALL PAVEMENT MARKINGS SHALL BE AS DIRECTED BY THE ENGINEER.

ALL INTERMITTENT RESURFACING LOCATIONS WILL BE DETERMINED IN THE FIELD BY THE ENGINEER.

THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

THE ENGINEER SHALL CONTACT WALLY CZARNY, AREA TRAFFIC FIELD ENGINEER AT (773) 685-4342 MINIMUM OF TWO (2) WEEKS PRIOR TO PLACEMENT OF PERMANENT PAVEMENT MARKINGS.

DOUBLE LANE MARKERS ARE TO BE USED AS SHOWN ON THE DISTRICT ONE DETAIL "TYPICAL APPLICATIONS - RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT)" SHOWN IN THE PLANS.

THE EXISTING ROADWAY TYPICAL SECTION IS ASSUMED TO HAVE A 3 INCH HOT-MIX ASPHALT OVERLAY ON TOP OF A TEN INCH CONCRETE BASE.

ALL INTERMITTENT RESURFACING LOCATIONS SHOWN IN THE PLANS ARE TWO (2) INCH MILL AND RESURFACE ONLY. THE MINIMUM WIDTH FOR INTERMITTENT RESURFACING SHALL BE THREE (3) FEET.

NO PATCHING OR RESURFACING IS TO BE DONE WITHIN FIFTY (50) FEET OF ANY RAILROAD CROSSING.

THE COST OF ANY PARTIAL OR FULL DEPTH PATCHING REQUIRED AFTER THE REMOVAL OF THE EXISTING 2 INCH HOT-MIX ASPHALT SURFACE SHALL BE PAID FOR IN ACCORDANCE WITH ARTICLE 109.04 OF THE STANDARD SPECIFICATIONS.

ANY DETECTOR LOOPS DAMAGED BY MILLING SHALL BE REPLACED IN KIND.
IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO QUANTIFY LOOP REPLACEMENTS NEEDED AND PROVIDE THE RESIDENT ENGINEER THIS INFORMATION PRIOR TO GRINDING OR REMOVAL.

ALL LOOP DETECTOR LOCATIONS SHALL BE CURB MARKED BY THE CONTRACTOR PRIOR TO MILLING FOR THE PURPOSE OF REESTABLISHING DETECTOR LOOP LAYOUT AFTER THE RESURFACING IS COMPLETED.

WHEN MILLED PAVEMENT IS OPEN TO TRAFFIC. THE MAXIMUM GRADE DIFFERENTIAL BETWEEN PASSES OF THE MILLING MACHINE SHALL NOT EXCEED 1 1/2 INCHES (40MM) WHERE THE SPEED LIMIT IS 45 MPH (80 KM/H) OR LESS AND 1 INCH (25 MM) WHERE THE SPEED LIMIT IS GREATER THAN 45 MPH (80 KM/H). WITH WRITTEN APPROVAL FROM THE RESIDENT ENGINEER, A MAXIMUM GRADE DIFFERENTIAL OF 3 INCHES (75 MM) MAY BE ALLOWED IF THE EDGE OF THE MILLING IS SLOPED A MINIMUM OF 1:3 (V:H).

OVERNIGHT LANE CLOSURES SHALL NOT BE ALLOWED FOR REHABILITATION PROJECTS INVOLVING DAYTIME MILLING AND RESURFACING OPERATIONS AND CLASS D PATCHING UNLESS OTHER CONDITIONS WARRANT EXTENDED LANE CLOSURES AS DETERMINED AND APPROVED IN WRITING BY THE ENGINEER OR AS PROVIDED FOR IN THE CONTRACT SPECIFICATIONS.

ANY MILLED PAVEMENT IS TO BE RESURFACED BY THE END OF EACH DAY AND OPEN TO TRAFFIC.

FILE	file hame = USER hame = Pengapi.		DESIGNED -	REVISEO -
01\p=	work\pwidat\pencep1\d0382486\HH4-	Eastern Lekeldyn	ORAWN -	REVISED -
		PLOT SCALE + 190,8000 1/ In.	CHECKED -	REVISED -
De Fau	de .	PLOT DATE + 4/3/2014	DATE -	REVISED -

STATE	OF	ILLINOIS		
DEPARTMENT OF TRANSPORTATION				

SCALE:

				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.			
INDEX OF	SHEETS, STATE STA		STANDAR	TANDARDS AND GENERAL		NOTES	VAR.	2014-025RS	LAKE	51	2
							CONTRACT		60Y11		
	SHEET	0F	SHEETS	STA.	TO STA.		ILLINOIS FED. AID PROJECT				