



J-HOOKS FOR SILT FILTER FENCE WILL NOT BE MEASURED FOR PAYMENT BUT SHALL BE INCLUDED IN THE UNIT PRICE BID FOR PERIMETER EROSION BARRIER.

AS A MINIMUM, SEDIMENT CONTROL STRUCTURES SHALL BE MAINTAINED AND/OR REPLACED AS REQUIRED WHEN SEDIMENT REACHES THE FOLLOWING LEVELS:

- PERIMETER EROSION BARRIER - 1/3 HEIGHT OF BARRIER
- INLET AND PIPE PROTECTION - 1/3 HEIGHT OF BARRIER
- INLET FILTERS - 1/4 FULL OR MORE THAN 1/2 OF FABRIC PORES ARE COVERED WITH SILT

STABILIZED CONSTRUCTION ENTRANCES SHALL BE PROVIDED AT ALL POINTS OF CONSTRUCTION EGRESS WHERE SEDIMENT CAN BE TRACKED ONTO PUBLIC ROADS. IN ADDITION, STABILIZED CONSTRUCTION ENTRANCES SHALL BE PROVIDED WHERE EQUIPMENT EXIT AREAS DESIGNATED AS "SPECIAL WASTE SITE" IN THE REMOVAL PLANS. STABILIZED CONSTRUCTION ENTRANCES SHALL CONFORM TO ILLINOIS URBAN MANUAL STANDARD DRAWING IL-630, AND PROPOSED LOCATIONS SHALL BE APPROVED BY THE ENGINEER. THE COST OF STABILIZED CONSTRUCTION ENTRANCES SHALL BE INCLUDED IN THE TRAFFIC CONTROL COST UNLESS OTHERWISE NOTED ON THE TRAFFIC CONTROL PLANS.

SEE GENERAL NOTES FOR SEEDING.

EROSION CONTROL BLANKET TO BE PLACED ON ALL DISTURBED SOIL WITHIN PROJECT LIMITS FOR THE WINTER SHUTDOWN.

LAYOUT	SPC	12/12/2013
DRAWN	SPC	12/12/2013
REVIEWED	JJM	2/26/2014

FILE NAME =	D2PACKE-HP5-sht-eros007L.dgn
USER NAME =	petke00954
DESIGNED -	SPG
DRAWN -	SPG
REVISOR -	
CHECKED -	JJM
DATE -	3/7/2014

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**EROSION AND SEDIMENT CONTROL  
RIVER DRIVE**

SCALE: 1" = 20'    SHEET NO.    OF    SHEETS    STA. 3000+50    TO    STA. 3011+50

F.A.U. R.T.E.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5756	(81-1)M	ROCK ISLAND	217	61
ILLINOIS FED. AID PROJECT			CONTRACT NO. 64J68	



EC-01