

TOTAL SIGNING BILL OF MATERIALS

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
SGN-01	INDEX OF SHEETS AND TOTAL BILL OF MATERIALS
SGN-02	REMOVAL SIGN SCHEDULE AND PROPOSED SIGN SCHEDULE
SGN-03 - SGN-07	SIGNING PLANS

LIST OF ILLINOIS DOT HIGHWAY STANDARDS

STD. NUMBER	DESCRIPTION
720001-01	SIGN PANEL MOUNTING DETAILS
720006-04	SIGN PANEL ERECTION DETAILS
720011-01	METAL POSTS FOR SIGNS, MARKERS & DELINEATORS
720021-02	SIGN PANELS EXTRUDED ALUMINUM TYPE
728001-01	TELESCOPING STEEL SIGN SUPPORT
729001-01	APPLICATIONS OF TYPES A & B METAL POSTS (FOR SIGNS & MARKERS)

PAY ITEM	DESCRIPTION	UNIT	TOTAL QUANTITY
50800105	REINFORCEMENT BARS	POUND	310
72000100	SIGN PANEL - TYPE 1	SQ FT	246
72000300	SIGN PANEL - TYPE 3	SQ FT	216
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	7
72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	5
72400310	REMOVE SIGN PANEL-TYPE 1	SQ FT	41
72400330	REMOVE SIGN PANEL-TYPE 3	SQ FT	168
72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	5
72400730	RELOCATE SIGN PANEL - TYPE 3	SQ FT	168
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	1,110
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	535
73000100	WOOD SIGN SUPPORT	FOOT	74
73400100	CONCRETE FOUNDATIONS	CU YD	2.8
73700100	REMOVE GROUND MOUNTED SIGN SUPPORT	EACH	17
73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	4

NOTE:

THE SIZE, DIMENSIONS AND QUANTITIES FOR THE FOUNDATIONS AND POSTS FOR THE SIGNS ON THE STEEL BREAKAWAY POSTS IS FOR BIDDING ESTIMATES ONLY. THE EXACT DESIGN SHALL BE DETERMINED AFTER THE FINAL GRADING HAS BEEN COMPLETED. ONCE FINAL GRADING HAS BEEN COMPLETED, THE CONTRACTOR SHALL CONTACT KRISTIE NYDEREK (815) 284-5474 OR KURT GLAZIER (815) 284-5478. THE STATE WILL HAVE 3 WEEKS TO PROVIDE THE SIGN SUPPORT DESIGNS TO THE CONTRACTOR. THE CONTRACTOR SHALL TAKE INTO ACCOUNT THE DESIGN AND FABRICATION TIME FOR THE LARGE PROPOSED GUIDE SIGNS (EB-3-BS-211A-P & WB-3-BS-222A-P) IN HIS SCHEDULE IN ORDER TO COMPLETE INSTALLATION WITHIN THE WORKING DAYS OF THIS CONTRACT. THE EXISTING SUPPORTS AND CONCRETE FOUNDATIONS FOR (EB-3-BS-211-R & WB-3-BS-222-R) SHALL BE REMOVED. THE CONTRACTOR SHALL RELOCATE THE EXISTING SIGN PANELS (EB-3-BS-211B-RL & WB-3-BS-222B-RL) TO THE LOCATION SHOWN IN THE PLANS ON NEW WOOD SIGN SUPPORTS UNTIL THE PROPOSED SIGNS ARE READY FOR INSTALLATION.

REMOVAL SIGN SCHEDULE

SIGN PLAN SHEET NUMBER	DESCRIPTION	SIGN CODE	ALIGNMENT NAME	STATION	OFFSET	PANEL WIDTH	PANEL HEIGHT	SIGN AREA	MOUNTING TYPE TS - BS - LP - TS - WP - SM	72400100	72400200	72400310	72400330	73700100	73700200
										REMOVE SIGN PANEL ASSEMBLY - TYPE A	REMOVE SIGN PANEL ASSEMBLY - TYPE B	REMOVE SIGN PANEL TYPE 1	REMOVE SIGN PANEL TYPE 3	REMOVE GROUND MOUNTED SIGN SUPPORT	REMOVE CONCRETE FOUNDATION - GROUND MOUNT
						FEET	FEET	SQ FT							
						EACH	EACH	SQ FT	SQ FT	EACH	EACH				
SGN-04	NO PARKING	EB-3-TS-203-R	RIVER DRIVE	3006+71	38' RT	2	2	4	TS					4	1
SGN-04	NO PARKING	EB-3-WP-204-R	RIVER DRIVE	3007+98	46' LT	2	2	4	TS					4	1
SGN-05	TO	WB-3-TS-205-R	RIVER DRIVE	3012+68	43.35' LT	2	1	2	TS					2	1
	EAST	WB-3-TS-206-R				2	1	2		2					
	INTERSTATE 74	WB-3-TS-207-R				2	2	4		4					
	DIRECTIONAL ARROW LEFT	WB-3-TS-208-R				1.75	1.25	2.2		2.2					
SGN-05	I-74/US 6 WEST DAVENPORT (EXISTING)	EB-3-BS-211-R	RIVER DRIVE	3013+11	61' RT				BS					2	2
SGN-05	I-74/US 6 WEST DAVENPORT (RELOCATED)	EB-3-WP-211B-RL	RIVER DRIVE	3013+00	61' RT				WP				84	2	
SGN-05	SPEED LIMIT 30 MPH	WB-3-TS-212-R	RIVER DRIVE	3015+50	43' LT	2	2.5	5	TS			5		1	
SGN-05	WELCOME TO MOLINE	WB-3-BS-212A-R	RIVER DRIVE	3015+84	98' LT	7	7.5	52.5	BS		1				
SGN-05	MOLINE CENTRE	WB-3-BS-212B-R	RIVER DRIVE	3015+99	86' LT	10.5	4	42	BS		1				
SGN-05	DO NOT ENTER (SEE NOTE BELOW)	WB-3-TS-311B-P	RIVER DRIVE	3015+86	78.71' LT	3.00	3.00	9	TS		1				
SGN-05	OBJECT MARKER (SEE NOTE BELOW)	WB-3-TS-311C-P	RIVER DRIVE	3015+91	80.18' LT	1.50	1.50	2.25	TS	1					
SGN-05	OBJECT MARKER (SEE NOTE BELOW)	WB-3-TS-311D-P	RIVER DRIVE	3016+00	78.60' LT	1.50	1.50	2.25	TS	1					
SGN-05	OBJECT MARKER (SEE NOTE BELOW)	WB-3-TS-311E-P	RIVER DRIVE	3016+09	76.96' LT	1.50	1.50	2.25	TS	1					
SGN-05	OBJECT MARKER (SEE NOTE BELOW)	WB-3-TS-311F-P	RIVER DRIVE	3016+19	75.51' LT	1.50	1.50	2.25	TS	1					
SGN-05	DO NOT ENTER (SEE NOTE BELOW)	WB-3-TS-311G-P	RIVER DRIVE	3016+24	72.98' LT	3.00	3.00	9	TS		1				
SGN-05	DO NOT ENTER (SEE NOTE BELOW)	WB-3-TS-311H-P	RIVER DRIVE	3016+27	73.18' LT	3.00	3.00	9	TS		1				
SGN-05	OBJECT MARKER (SEE NOTE BELOW)	WB-3-TS-311I-P	RIVER DRIVE	3016+30	78.04' LT	1.50	1.50	2.25	TS	1					
SGN-05	OBJECT MARKER (SEE NOTE BELOW)	WB-3-TS-311J-P	RIVER DRIVE	3016+38	82.72' LT	1.50	1.50	2.25	TS	1					
SGN-05	OBJECT MARKER (SEE NOTE BELOW)	WB-3-TS-311K-P	RIVER DRIVE	3016+46	87.69' LT	1.50	1.50	2.25	TS	1					
SGN-05	NO PARKING THIS SIDE OF STREET	WB-3-TS-213-R	RIVER DRIVE	3016+52	49' RT	1	1.5	1.5	TS			1.5		1	
SGN-06	NO PARKING HERE TO CORNER	WB-3-TS-220-R	20TH ST	36+30	15' LT	1	1.5	1.5	TS			1.5		1	
SGN-06	NO PARKING HERE TO CORNER	WB-3-TS-221-R	20TH ST	36+38	18' RT	1	1.5	1.5	TS			1.5		1	
SGN-06	I-74/US 6 WEST DAVENPORT (EXISTING)	WB-3-BS-222-R	RIVER DRIVE	3019+45	63' LT				BS					2	2
SGN-06	I-74/US 6 WEST DAVENPORT (RELOCATED)	WB-3-WP-222B-RL	RIVER DRIVE	3020+40	63' LT				BS				84	2	
SGN-06	DO NOT ENTER	WB-3-TS-223-R	RIVER DRIVE	3020+41	9.48' LT	2.5	2.5	6.25	TS			6.25		1	
SGN-07	DO NOT ENTER	EB-R38-TS-215-R	RAMP (N-3)	173+96.57	36.83' LT	2.5	2.5	6.25	TS			6.25		1	
TOTAL										7	5	41	168	17	4

REMOVAL NOTE:

THE SIGNS AND POSTS LOCATED AT THE RAMP TERMINATION POINTS SHALL BE REMOVED WHILE THE STABILIZED CONSTRUCTION ENTRANCE IS IN USE. THE SIGNS AND POSTS SHALL BE REINSTALLED AFTER 20TH STREET CONSTRUCTION IS COMPLETE AND THE STABILIZED CONSTRUCTION ENTRANCE IS REMOVED.



LAYOUT	MPV	7/1/2011
DRAWN	MPV	2/5/2013
REVIEWED	MTH	3/14/2014

FILE NAME =	USER NAME = petke00954	DESIGNED - MPV	REVISED -
D2PACKE-HP5-sht-sign001.dgn		DRAWN - MPV	REVISED -
		CHECKED - MTH	REVISED -
PLOT DATE = 03/25/2014		DATE - 3/7/2014	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIGNING PLAN
TOTAL SIGNING BILL OF MATERIALS
AND REMOVAL SCHEDULE

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5756	(81-1)M	ROCK ISLAND	217	119
ILLINOIS FED. AID PROJECT			CONTRACT NO. 64J68	

SGN-01