

SIDEWALK SCHEDULE FOR NEW RAMP INSTALLATION						
LOCATION SIDE STREET QUAD	STANDARD NUMBER	PCC SIDEWALK 4"	DETECTABLE WARNINGS	SIDEWALK REMOVAL	SOD, SALT TOLERANT	SUPPLEMENTAL WATERING
			US 34 ACCESS			
		SQ FT	SQ FT	SQ FT	SQ YD	UNIT
HIGH ST. NE QUAD	424001-07	25.0	10.0	N/A	5.0	0.05
MAIN ST. SE QUAD	424001-07	25.0	10.0	25.0	5.0	0.05
TOTAL		50.0	20.0	25.0	10.0	0.1

MAINLINE SCHEDULE														
STA. TO STA.	LENGTH	WIDTH	AREA	HMA SURF CSE	LEVEL BINDER (MM)	LEVEL BINDER (MM)	HMA SURF REM 2 1/4"	MIX FOR JTS, CRACKS & FLGWS	BIT. MAT'L (PR CT)	ACG SHLD TY B	TEMP RAMP			
												FT	FT	SO YD
US 34/6TH STREET INTERSECTION	39+16	43+66												
	43+66	72+41	2875		32	2187.0	183.7	91.9	1.1	2187.0	0.7	1476.2	16.4	18.0
GAP (SN 006-0135)	72+41	75+90	348.63			10222.2	858.7	429.3	5.1	10222.2	3.1	6900.0	104.8	18.0
	75+90	93+00	1710		32	6080.0	510.7	255.4	3.0	6080.0	1.8	4104.0	62.3	18.0
	93+00	293+50	20050		26	57922.2	4865.5	2432.7	29.0	57922.2	17.4	39097.5	730.7	18.0
TURN LANES														
T.R. 241			266.7			22.4	11.2	0.1	266.7	0.1	180.0	30.0		
T.R. 227			266.7			22.4	11.2	0.1	266.7	0.1	180.0	30.0		
COUNTY HWY 27 (2)			500.0			42.0	21.0	0.3	500.0	0.2	337.5	30.0		
T.R. 209 (2)			533.3			44.8	22.4	0.3	533.3	0.2	360.0	30.0		
COUNTY HWY 5			250.0			21.0	10.5	0.1	250.0	0.1	168.8	30.0		
TOTALS			78228.1	6571.2	3285.6	39.1	78228.1	23.5	52804.0	1117.4	72.0			

PAVEMENT MARKERS																				
LOCATION	PAINT 4" WHITE	PAINT 4" YELL	PAINT 6" YELL	THERM 4" WHITE	THERM 4" YELL	THERM 8" WHITE	THERM 12" WHITE	THERM 12" YELL	THERM 24" WHITE	THERM LTR. & SYM.	TEMP MARK 4"	TEMP MARK 6"	TEMP MARK 8"	TEMP MARK 12"	TEMP MARK 24"	TEMP LTR. & SYM.	SHORT- TERM MARK	WORK ZONE PAVT MARK REM	RAISED REFLECTIVE PVMT MARK	
STA	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SO. FT.	FOOT	FOOT	FOOT	FOOT	FOOT	SO. FT.	FOOT	SO. FT.	EACH	
BUREAU COUNTY																				
39+16 TO 43+66 (US 34/6TH STREET INTERSECTION)				749.9	1963.8	1058.7	569.9	107.6	143.7	93.6	2713.7		1058.7	677.5	143.7	93.6	4587.0	504.6		
69+58.77 (CR 1700)					230.0	187.0	188.0	36.0	36.0		230.0		187.0	224.0	36.0					
137+10.19 (CR 1800)					494.0	317.0	93.0	18.0	34.0		490.0		317.0	111.0	34.0					
207+00 (CR 1900)						259.0	112.0		34.0				259.0	112.0	34.0					
43+66 TO 72+41	5750		718.8								5750.0	718.8					862.5	94.9	36.0	
72+41 TO 75+90 (BRIDGE)	698	698									698.0	87.3					104.7	3.8	4.0	
75+90 TO 93+00	3420		427.5								3420.0	427.5					513.0	188.1	21.0	
93+00 TO 293+50	40100		5012.5								40100.0	5012.5					8020.0	661.0	251.0	
NO PASSING ZONES (1)																				
59+50 TO 79+56 (SOLID YELLOW)	2025										2025.0									
69+00 TO 88+01 (SOLID YELLOW)	1919										1919.0									
107+56 TO 114+12 (LT SOLID YELLOW)	856										856.0									
145+80 TO 153+19 (RT SOLID YELLOW)	929										929.0									
153+83 TO 163+75 (LT SOLID YELLOW)	1242										1242.0									
258+79 TO 263+02 (RT SOLID YELLOW)	533										533.0									
263+02 TO 275+16 (DOUBLE SOLID YELLOW)	2428										2428.0									
275+16 TO 279+91 (LT SOLID YELLOW)	595										595.0									
TURN LANES																				
32+34 TO 33+34						100				31.6				100.0					31.6	
79+37 TO 80+37						100				31.6				100.0					31.6	
135+22 TO 136+22						100				31.6				100.0					31.6	
137+67 TO 138+67						100				31.6				100.0					31.6	
205+39 TO 206+39						100				31.6				100.0					31.6	
282+83 TO 283+83						100				31.6				100.0					31.6	
285+36 TO 286+36						100				31.6				100.0					31.6	
DOUBLE APPLICATION FOR PAINT*		60495	698	6159																
T.R. 227 B (MEDIAN & ISLAND)					727.0															
GRAND TOTAL		120990	1396	12318	750	3415	2522	963	162	248	315	63929	6246	2522	1125	248	315	14087	1452	312

*ABOVE QUANTITIES INCLUDE DISTANCES TO COVER DOUBLE APPLICATION FOR PAINTED PAVEMENT MARKINGS
(1) R.E. TO VERIFY NO PASSING ZONES PRIOR TO MILLING OPERATIONS

FILE NAME =	USER NAME = \$USER*	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES	F.A.S RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
\$FILEL\$		DRAWN -	REVISED -			1249	(23)RS-7	BUREAU	16	8	
\$MODELNAME\$		CHECKED -	REVISED -			CONTRACT NO. 66A02					
		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					
				SCALE:	SHEET OF SHEETS	STA.	TO STA.				