

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				0004	0014	0021
				ROADWAY	STRUCTURE	ELECTRICAL
				80/20 URBAN	80/20 URBAN	80/20 URBAN
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	16.96	16.96		
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	901	901		
40600982	HOT - MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	1415	1415		
40600990	TEMPORARY RAMP	SO YD	233	233		
40603560	POLYMERIZED HOT - MIX ASPHALT SURFACE COURSE, MIX "E", N50	TON	4647	4647		
40800050	INCIDENTAL HOT - MIX ASPHALT SURFACING	TON	58	58		
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SO FT	84.5	84.5		
42400800	DETECTABLE WARNINGS	SO FT	20	20		
44000152	HOT - MIX ASPHALT SURFACE REMOVAL, 3/4"	SO YD	2411	2411		
44000155	HOT - MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	59642	59642		
44000600	SIDEWALK REMOVAL	SO FT	84.5	84.5		
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SO YD	112	112		
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SO YD	16	16		
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SO YD	27	27		

14

FILE NAME : 0458665-shc-details.dgn	USER NAME : aubreyg	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / 1"	CHECKED -	REVISED -
	PLOT DATE = 3/21/2014	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

F.A.U. RTE. 6791	SECTION 126RS-4	COUNTY KNOX	TOTAL SHEETS 76	SHEET NO. 3
CONTRACT NO. 68865			ILLINOIS FED. AID PROJECT	