SCHEDULE OF QUANTITIES

REMOVAL

PCC/HMA SURFACE REMOVAL – BUTT JOINT

	STATION	TO	STATION	THICKNESS (IN)	LENGTH (FOOT)	TOTAL WIDTH (FEET)	AREA (SQ YD)	HMA SURFACE REMOVAL - BUTT JOINT 40600982 (SQ YD)	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT 40600985 (SQ YD)
NB URBAN	94+46.24		95+06.24	2.00	60.00	16.0	106.7		106.7
NB URBAN	99+91.95		100+51.95	2.00	60.00	16.0	106.7		106.7
I-55 RAMP B	18+71.00		19+31.00	2.00	60.00	26.0	173.3		173.3
NB URBAN	122+58.61		123+18.61	2.00	60.00	16.0	106.7		106.7
NB URBAN	126+83.61		127+43.61	2.00	60.00	16.0	106.7		106.7
MEDIAN CROSSOVER			149+04.00	2.00	34.40	4.6	17.6	17.6	
TR 181 RAMP C	8+35.00		8+95.00	2.00	60.00	26.0	173.3		173.3
TR 181 RAMP B	6+39.00		6+99.00	2.00	60.00	26.0	173.3		173.3
NB RURAL	290+25.00		290+85.00	2.00	60.00	16.0	106.7		106.7
SB RURAL	290+70.00		291+30.00	2.00	60.00	16.0	106.7		106.7
							NB URBAN	17.6	946.7
							NB RURAL	0.0	106.7
							SB RURAL	0.0	106.7
							TOTAL	17.6	1053.3
							ROUNDED	20.0	1170.0

PAVEMENT MARKING REMOVAL

		STATION	TO	STATION	# OF WHITE STRIPES	# OF YELLOW STRIPES	LENGTH (FOOT)	STRIPE WIDTH (IN)	PAVEMENT MARKING REMOVAL 78300100 (SQ FT)	
									WHITE	YELLOW
	NORTHBOUND URBAN									
	NB URBAN LL	42+00.00		44+00.00	0.33	0.00	200.0	4	22.0	0.0
SN 057-0215	NB URBAN CL	95+12.00		99+86.00	0.25	0.00	474.0	4	39.5	0.0
SN 057-0217	NB URBAN CL	123+25.00		126+78.00	0.25	0.00	353.0	4	29.4	0.0
	NORTHBOUND RURAL									
SN 057-0211	NB RURAL CL	291+36.00		293+24.00	0.25	0.00	188.0	4	15.7	0.0
SN 057-0209	NB RURAL CL	303+47.00		306+01.00	0.25	0.00	254.0	4	21.2	0.0
	SOUTHBOUND RURAL									
SN 057-0210	SB RURAL CL	290+91.00		293+09.00	0.25	0.00	218.0	4	18.2	0.0
SN 057-0208	SB RURAL CL	303+34.00		306+14.00	0.25	0.00	280.0	4	23.3	0.0
							NB URBAN TOTAL		90.9	0.0
							NB URBAN ROUNDED		100.0	0.0
							NB RURAL TOTAL		36.9	0.0
							NB RURAL ROUNDED		40.0	0.0
							SB RURAL TOTAL		41.5	0.0
							SB RURAL ROUNDED		50.0	0.0
							TOTAL		190.0	

PCC SHOULDERS

	STATION	INSIDE WIDTH (FOOT)	STATION	OUTSIDE WIDTH (FOOT)	LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ YD)	PAVED SHOULDER REMOVAL 44004250 (SQ YD)	PCC SHOULDERS 8" 48300300 (SQ YD)	PCC SHOULDERS 10 3/4" 48300515 (SQ YD)	PCC SHOULDERS 12" 48300700 (SQ YD)
I-55 GORE	44+45.00		48+27.00	MEASURED FROM CADD			455.0	455.0		455.0	
NB URBAN	42+00.00	0.0	48+27.00	10.0	627.00	10.0	696.7	696.7	696.7		
NB URBAN	48+27.00	6.0	48+87.00	10.0	60.00	16.0	106.7	106.7			106.7
NB URBAN	176+20.00	6.0	176+80.00	10.0	60.00	16.0	106.7	106.7			106.7
NB URBAN	176+80.00	6.0	180+30.00	10.0	350.00	16.0	622.2	622.2	622.2		
NB URBAN	180+30.00	6.0	180+90.00	10.0	60.00	16.0	106.7	106.7			106.7
NB RURAL	293+30.00	6.0	303+41.00	10.0	1011.00	16.0	1797.3	1,797.3	1,797.3		
SB RURAL	234+91.00	6.0	235+16.00	10.0	25.00	16.0	44.4	44.4	44.4		
SB RURAL	235+16.00	6.0	235+76.00	10.0	60.00	16.0	106.7	106.7			106.7
SB RURAL	293+15.00	6.0	303+28.00	10.0	1013.00	16.0	1800.9	1,800.9	1,800.9		
				NORTHBOUND URBAN TOTAL				2,093.9	1,318.9	455.0	320.1
				NORTHBOUND URBAN ROUNDED				2,100.0	1,320.0	460.0	330.0
				NORTHBOUND RURAL TOTAL				1,797.3	1,797.3	0.0	0.0
				NORTHBOUND RURAL ROUNDED				1,800.0	1,800.0	0.0	0.0
				SOUTHBOUND RURAL TOTAL				1,952.0	1,845.3	0.0	106.7
				SOUTHBOUND RURAL ROUNDED				1,960.0	1,850.0	0.0	110.0
				ROUNDED TOTAL				5,860.0	4,970.0	460.0	440.0

*PCC SHOULDERS 8" SHALL BE 10 3/4" (10") AT EOP TAPERED DOWN TO 6" AT EOS

**PCC SHOULDERS 12" TRANSITION FROM 10 3/4" (10") AT EOP TO 12 3/4" (12") AT EOP

RAISED REFLECTIVE PAVEMENT MARKERS REMOVAL

		STATION	TO	STATION		LENGTH (FOOT)	RAISED PAVEMENT MARKERS REMOVAL 78300200 (EACH)
NB URBAN		50+67.00		92+66.24		4199.24	105.0
NB URBAN		102+31.95		120+78.61		1846.66	47.0
NB URBAN		129+23.61		156+36.57		2712.96	68.0
STA EQ		156+36.57		156+23.97		0.00	
NB URBAN		156+23.97		174+40.00		1816.03	46.0
TR 181 C		0+00.00		2+94.75		294.75	15.0
TR 181 C		2+94.75		6+55.00		360.25	38.0
NB URBAN		182+70.00		198+61.67		1591.67	40.0
NB RURAL		198+61.67		288+90.00		9028.33	226.0
SB RURAL		237+56.00		288+45.00		5089.00	128.0
				NB URBAN TOTAL			359.0
				NB URBAN ROUNDED			360.0
				NB RURAL TOTAL			226.0
				NB RURAL ROUNDED			230.0
				SB RURAL TOTAL			128.0
				SB RURAL ROUNDED			130.0
				TOTAL			720.0