

# SCHEDULE OF QUANTITIES

## GUARDRAIL

		STATION	TO	STATION	LENGTH (FOOT)	STEEL PLATE BEAM GUARDRAIL TYPE A, 6 FOOT POSTS 63000001 (FOOT)	TRAFFIC BARRIER TERMINAL, TYPE 6 63100085 (EACH)	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT 63100167 (EACH)	GUARDRAIL MARKERS, TYPE A 78200410 (EACH)	BARRIER WALL MARKERS, TYPE C 78200530 (EACH)	TERMINAL MARKER - DIRECT APPLIED 78201000 (EACH)
<b>NORTHBOUND URBAN</b>											
NB URBAN	RT	94+34.53		94+84.53	50.00			1.0			1.0
NB URBAN	RT	94+84.53		95+71.35	87.50	87.5			2.0		
NB URBAN	RT	95+71.35		96+14.50	43.15		1.0				
NB URBAN	RT	96+14.50		98+84.59	270.09					3.0	
NB URBAN	LT	93+09.79		93+59.79	50.00			1.0			1.0
NB URBAN	LT	93+59.79		95+62.91	200.00	200.0			3.0		
NB URBAN	LT	95+62.91		96+06.06	43.15		1.0				
NB URBAN	LT	96+06.06		98+79.20	273.14					3.0	
NB URBAN	RT	121+69.48		122+19.48	50.00			1.0			1.0
NB URBAN	RT	122+19.48		123+82.02	162.50	162.5			3.0		
NB URBAN	RT	123+82.02		124+25.17	43.15		1.0				
NB URBAN	RT	124+25.17		125+75.54	150.37					2.0	
NB URBAN	LT	121+30.74		121+80.74	50.00			1.0			1.0
NB URBAN	LT	121+80.74		123+80.64	200.00	200.0			3.0		
NB URBAN	LT	123+80.64		124+23.79	43.15		1.0				
NB URBAN	LT	124+23.79		125+73.91	150.12					2.0	
<b>NORTHBOUND RURAL</b>											
NB RURAL	LT	289+13.60		289+63.60	50.00			1.0			1.0
NB RURAL	LT	289+63.60		291+64.09	200.00	200.0			3.0		
NB RURAL	LT	291+64.09		292+07.24	43.15		1.0				
NB RURAL	LT	292+07.24		292+75.28	68.04					1.0	
NB RURAL	RT	289+73.74		290+23.74	50.00			1.0			1.0
NB RURAL	RT	290+23.74		291+88.95	162.50	162.5			3.0		
NB RURAL	RT	291+88.95		292+32.10	43.15		1.0				
NB RURAL	RT	292+32.10		292+99.64	67.54					1.0	
NB RURAL	RT	300+83.89		301+33.89	50.00			1.0			1.0
NB RURAL	RT	301+33.89		303+23.92	187.50	187.5			3.0		
NB RURAL	RT	303+23.92		303+67.07	43.15		1.0				
NB RURAL	RT	303+67.07		305+15.64	148.57					2.0	
NB RURAL	LT	301+14.51		301+64.51	50.00			1.0			1.0
NB RURAL	LT	301+64.51		303+40.29	175.00	175.0			3.0		
NB RURAL	LT	303+40.29		303+83.44	43.15		1.0				
NB RURAL	LT	303+83.44		305+30.93	147.49					2.0	
<b>SOUTHBOUND RURAL</b>											
SB RURAL	LT	291+60.65		292+30.17	69.52					1.0	
SB RURAL	LT	292+30.17		292+73.32	43.15		1.0				
SB RURAL	LT	292+73.32		293+96.37	125.00	125.0			3.0		
SB RURAL	LT	293+96.37		294+46.37	50.00			1.0			1.0
NB RURAL	RT	291+86.27		292+53.68	67.41					1.0	
SB RURAL	RT	292+53.68		292+96.83	43.15		1.0				
SB RURAL	RT	292+96.83		295+20.90	225.00	225.0			3.0		
SB RURAL	RT	295+20.90		295+70.90	50.00			1.0			1.0
NB URBAN TOTAL						650.0	4.0	4.0	11.0	10.0	4.0
NB RURAL TOTAL						725.0	4.0	4.0	12.0	6.0	4.0
SB RURAL TOTAL						350.0	2.0	2.0	6.0	2.0	2.0
TOTAL						1,725.0	10.0	10.0	29.0	18.0	10.0

## GUARDRAIL REMOVAL

		STATION	TO	STATION	LENGTH (FOOT)	GUARDRAIL REMOVAL 63200310 (FOOT)
<b>NORTHBOUND URBAN</b>						
NB URBAN	RT	92+80.00		96+28.00	348.00	348.0
NB URBAN	LT	93+28.00		96+20.00	292.00	292.0
NB URBAN	RT	121+01.00		124+38.00	337.00	337.0
NB URBAN	LT	121+62.00		124+37.00	275.00	275.0
<b>NORTHBOUND RURAL</b>						
NB RURAL	LT	288+76.00		292+10.00	334.00	334.00
NB RURAL	RT	288+79.00		292+46.00	367.00	367.00
NB RURAL	RT	292+87.00		294+54.00	167.00	167.00
NB RURAL	RT	299+88.00		303+82.00	394.00	394.00
NB RURAL	LT	300+57.00		303+98.00	341.00	341.00
<b>SOUTHBOUND RURAL</b>						
SB RURAL	LT	290+12.00		291+75.00	163.00	163.00
SB RURAL	LT	292+15.00		295+53.00	338.00	338.00
SB RURAL	RT	292+38.00		295+78.00	340.00	340.00
SB RURAL	LT	302+90.00		304+29.00	139.00	139.00
NB URBAN TOTAL						1,252.0
NB RURAL TOTAL						1,603.0
SB RURAL TOTAL						980.0
ROUNDED TOTAL						3,840.0