

SCHEDULE OF QUANTITIES

PIPE UNDERDRAINS (SHEET 3 OF 3)

SOUTHBOUND

	STATION	TO	STATION	MAINLINE	PIPE UNDERDRAINS, 4"		MAINLINE
				SHOULDER REMOVAL AND REPLACEMENT 11" 60100076 (FEET)	DRIVING LANE (FOOT)	PASSING LANE (FOOT)	PIPE UNDERDRAIN REMOVAL Z0040530 (FOOT)
SB RURAL	234+91.00		239+00.00	648.0	408.0	408.0	816.0
SB RURAL	239+00.00		244+00.00	1,000.0	500.0	500.0	1,000.0
SB RURAL	244+00.00		249+00.00	1,000.0	500.0	500.0	1,000.0
SB RURAL	249+00.00		254+00.00	1,000.0	500.0	500.0	1,000.0
SB RURAL	254+00.00		259+00.00	1,000.0	500.0	500.0	1,000.0
SB RURAL	259+00.00		264+00.00	1,000.0	500.0	500.0	1,000.0
SB RURAL	264+00.00		269+00.00	1,000.0	500.0	500.0	1,000.0
SB RURAL	269+00.00		274+00.00	1,000.0	500.0	500.0	1,000.0
SB RURAL	274+00.00		279+00.00	1,000.0	500.0	500.0	1,000.0
SB RURAL	279+00.00		284+00.00	1,000.0	500.0	500.0	1,000.0
SB RURAL	284+00.00		289+00.00	1,000.0	500.0	500.0	1,000.0
SB RURAL	289+00.00		290+88.00	370.4	188.3	188.2	376.5
SB RURAL	293+12.00		299+00.00	0.0	592.4	590.3	1,182.7
SB RURAL	299+00.00		303+34.00	0.0	437.2	435.7	872.9
SB RURAL TOTAL				11,018.4	6,625.9	6,622.2	13,248.1
SB RURAL ROUNDED				11,020.0	13,250.0		13,250.0

	STATION	EROSION CONTROL BLANKET 25100630 (SQ YD)	CONCRETE HEADWALLS FOR PIPE DRAINS 60100060 (EACH)	DRIVING LANE OUTLET	PASSING LANE OUTLET	PIPE UNDERDRAINS, 4"		CONCRETE HEADWALL REMOVAL SPECIAL X5012650 (EACH)	DRIVING LANE	PASSING LANE
				SHOULDER REMOVAL AND REPLACEMENT 11" 60100076 (FEET)	SHOULDER REMOVAL AND REPLACEMENT 11" 60100076 (FEET)	(SPECIAL) 60108100	PIPE UNDERDRAIN REMOVAL Z0040530 (FOOT)		PIPE UNDERDRAIN REMOVAL Z0040530 (FOOT)	
SB RURAL	235+00.00	8.0	2.0	10.0	6.0	21.2	22.0	2.0	28.8	19.7
SB RURAL	239+00.00	8.0	2.0	10.0	6.0	19.8	16.8	2.0	23.3	15.5
SB RURAL	244+00.00	8.0	2.0	10.0	6.0	21.1	16.3	2.0	22.7	15.4
SB RURAL	249+00.00	8.0	2.0	10.0	6.0	21.4	21.7	2.0	22.7	15.3
SB RURAL	254+00.00	8.0	2.0	10.0	6.0	19.2	17.3	2.0	22.8	15.2
SB RURAL	260+00.00	4.0	1.0	10.0	0.0	25.2	0.0	1.0	19.8	0.0
SB RURAL	266+10.00	4.0	1.0	0.0	6.0	0.0	16.0	1.0	0.0	17.4
SB RURAL	266+15.00	4.0	1.0	10.0	0.0	19.7	0.0	1.0	23.2	0.0
SB RURAL	269+00.00	8.0	2.0	10.0	6.0	23.3	17.2	2.0	22.3	18.3
SB RURAL	274+00.00	8.0	2.0	10.0	6.0	22.4	17.8	2.0	23.1	18.3
SB RURAL	279+00.00	8.0	2.0	10.0	6.0	22.4	17.4	2.0	24.1	18.3
SB RURAL	284+00.00	8.0	2.0	10.0	6.0	20.9	18.3	2.0	20.2	19.4
SB RURAL	289+00.00	8.0	2.0	10.0	6.0	20.4	18.2	2.0	21.9	19.4
SB RURAL	290+88.00	8.0	2.0	0.0	0.0	20.3	21.3	0.0	0.0	0.0
SB RURAL	293+12.00	8.0	2.0	0.0	0.0	24.1	17.1	0.0	0.0	0.0
SB RURAL	299+00.00	8.0	2.0	0.0	0.0	29.8	26.2	2.0	26.2	20.0
SB RURAL TOTAL		116.0	29.0	120.0	66.0	331.2	263.6	25.0	301.1	212.2
SB RURAL ROUNDED		120.0	30.0			190.0	600.0	30.0		520.0

PIPE UNDERDRAINS SUMMARY

	EROSION CONTROL BLANKET 25100630 (SQ YD)	CONCRETE HEADWALLS FOR PIPE DRAINS 60100060 (EACH)	PIPE UNDERDRAINS, 4" 60107600 (FOOT)	PIPE UNDERDRAINS, 4" (SPECIAL) 60108100 (FOOT)
NB URBAN	240.0	60.0	28,870.0	1,140.0
NB RURAL	170.0	50.0	20,540.0	880.0
SB RURAL	120.0	30.0	13,250.0	600.0
TOTAL	530.0	140.0	62,660.0	2,620.0

PIPE UNDERDRAINS REMOVAL SUMMARY

		SHOULDER REMOVAL AND REPLACEMENT 11" 60100076 (FEET)		CONCRETE HEADWALL REMOVAL SPECIAL X5012650 (EACH)	PIPE UNDERDRAIN REMOVAL Z0040530 (FOOT)	
		SUB-TOTAL	TOTAL	TOTAL	SUB-TOTAL	TOTAL
NB URBAN	MAINLINE	27,180.0	27,610.0	60.0	28,870.0	30,030.0
	OUTLETS	430.0			1,160.0	
NB RURAL	MAINLINE	18,540.0	18,860.0	50.0	20,540.0	21,500.0
	OUTLETS	320.0			960.0	
SB RURAL	MAINLINE	11,020.0	11,210.0	30.0	13,250.0	13,770.0
	OUTLETS	190.0			520.0	
TOTAL		57,680.0		140.0	65,300.0	