

LOCATION OF WORK: FAI 39 NORTHBOUND URBAN INTERSTATE STA. 42+00 TO STA. 198+62 MCLEAN COUNTY 90% FEDERAL, 10% STATE CONSTRUCTION TYPE CODE: 0004

FAI 39 NORTHBOUND RURAL INTERSTATE STA. 198+62 TO STA. 303+47 MCLEAN COUNTY 90% FEDERAL, 10% STATE 0004

FAI 39 SOUTHBOUND RURAL INTERSTATE STA. 234+91 TO STA. 303+34 MCLEAN COUNTY 90% FEDERAL, 10% STATE 0004

CODE NO.	ITEM	UNIT	TOTAL QUANTITY			
35800100	PREPARATION OF BASE	SQ YD	900.0	660.0	110.0	130.0
35800200	AGGREGATE BASE REPAIR	TON	270.0	270.0	0.0	0.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	30,990.0	15,350.0	9,830.0	5,810.0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	20.0	20.0	0.0	0.0
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	1,170.0	950.0	110.0	110.0
40600990	TEMPORARY RAMP	SQ YD	2,140.0	2,140.0	0.0	0.0
40603092	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, FG, N90	TON	16,830.0	8,320.0	5,410.0	3,100.0
40603243	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, FG, N90	TON	10,210.0	5,160.0	3,180.0	1,870.0
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	9,090.0	4,650.0	2,790.0	1,650.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	35.0	15.0	10.0	10.0
40800030	AGGREGATE (PRIME COAT)	TON	1.0	0.4	0.3	0.3
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	145.0	55.0	45.0	45.0
44004250	PAVED SHOULDER REMOVAL	SQ YD	5,860.0	2,100.0	1,800.0	1,960.0
44200559	CLASS A PATCHES, TYPE IV, 10 INCH	SQ YD	6,910.0	0.0	3,180.0	3,730.0

N • DENOTES SPECIALTY ITEM