INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	INDEX OF SHEETS/LIST OF STANDARDS
2	GENERAL NOTES
3	LOCATION MAPS
4	SUMMARY OF QUANTITIES
5	EXISTING TYPICAL SECTIONS
6	SCHEDULE OF QUANTITIES

GENERAL NOTES

G N 100

ENGLISH UNITS OF MEASUREMENT SHALL GOVERN OVER AND SUPERSEDE ANY METRIC UNITS SHOWN IN THIS CONTRACT. WHERE INCLUDED, METRIC UNITS ARE FOR INFORMATION ONLY.

GN 406H Mixture Requirements

Location	US 24	US 24	
Mixture Use	Surface and Incid.	Class D patch	
AC/PG	PG 64-22	PG 64-22	
RAP % (Max)	See RAP-RAS S.P.	See RAP-RAS S.P.	
Design Air Volds	4.0% @ Ndes=70	4.0% @ Ndes=70	
Mix Comp(Gradation)	IL 9.5	IL 19.0 FG	
Friction Aggregate	Mix C	N,A,	

G.N.-442B

THE PATCHING SCHEDULES INCLUDED IN THE PLANS REPRESENT THE BEST INFORMATION AVAILABLE AT THE TIME OF COMPLETION OF THE PLANS FOR LETTING. VARIATIONS IN LOCATION AND SIZES OF BOTH FULL-DEPTH AND PARTIAL-DEPTH PATCHES MAY OCCUR.

G.N.-667

THE RESIDENT ENGINEER SHALL CONTACT THE PROGRAM DEVELOPMENT CHIEF OF SURVEYS PRIOR TO THE PRE-CONSTRUCTION CONFERENCE FOR INSTRUCTION AS TO SETTING OF TEMPORARY OR PERMANENT TIES FOR CENTERLINE ALIGNMENT CONTROL SURVEY MARKERS (PC'S, PT'S, AND PI'S). PROJECT IMPLEMENTATION PERSONNEL WILL BE RESPONSIBLE FOR SETTING THESE MARKERS.

G.N.-1004.01

COARSE AGGREGATE GRADATION CA-10 MAY BE USED WHENEVER COARSE AGGREGATE CA-6 IS SPECIFIED IN THE STANDARD SPECIFICATIONS.

NO COMMITMENTS

LIST OF STANDARDS

STANDARD NUMBER	NAME OF STANDARD				
000001-06	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS				
001001-02	AREAS OF REINFORCEMENT BARS				
001006	DECIMAL OF AND INCH AND OF A FOOT				
420701-02	PAVEMENT FABRIC				
421001-02	BAR REINFORCEMENT FOR CRC PAVEMENT				
421101-09	24' (7.2 m) CRC PAVEMENT (WITH WIDE FLANGE BEAM TERMINAL JOINT)				
442001-04	CLASS A PATCHES				
442201-03	CLASS C & D PATCHES				
701101-04	OFF-ROAD OPERATIONS, MULTILANE, 15' TO 24" FROM PAVEMENT EDGE				
701201-04	LANE CLOSURE, 2L, 2W DAY ONLY				
701301-04	LANE CLOSURE, 2L, 2W SHORT TIME OPERATIONS				
701400-07	APPROACH TO LANE CLOSURE FREEWAY/EXPRESSWAY				
701401-08	LANE CLOSURE, FREEWAY / EXPRESSWAY				
701426-06	LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPERATIONS, FOR SPEEDS \geq 45 MPH				
701901-03	TRAFFIC CONTROL DEVICES				

* MCLEAN & DEWITT COUNTIES ** FAP 317 & FAP 322

FILE NAME :	USER NAME = operlook,d	DESIGNED -	REVISED -		INDEX OF SHEETS, LIST OF	F.A.P. SECTION COUNTY TOTAL SHEET
ci\p=_work\p=idot\cearlook;d\d8379886\8	170434-sht-gennate.dgn	DRAWN -	REVISED -	STATE OF ILLINOIS	STANDARDS & GENERAL NOTES	05 PATCHING 2014-1 - 6 2
1	PLOT SCALE = 40.0000 1/ in-	CHECKED -	REVISED ~	DEPARTMENT OF TRANSPORTATION	STANDARDS & GENERAL NOTES	CONTRACT NO. 70A34
MCDELNAME	PLOT DATE = 3/19/2814	DATE -	REVISED -		SCALE: N/A SHEET 1 OF 1 SHEETS STA. TO STA.	ILLINOIS FED. AID PROJECT