

IL 267 TEMPORARY RAMPS				
LOCATION OF TEMPORARY RAMP	LENGTH OF RAMP	WIDTH OF RAMP	AREA OF RAMP	TEMPORARY RAMP
	(FOOT)	(FOOT)	(SQ FOOT)	40600990 (SQUARE YARD)
<b>IL 267</b>				
STA. 101+14.67	5.0	46	230.0	25.6
STA. 106+12.29 NORTHBOUND	5.0	14	70.0	7.8
STA. 106+12.29 SOUTHBOUND	5.0	14	70.0	7.8
STA. 108+67.00 NORTHBOUND	5.0	14	70.0	7.8
STA. 108+67.00 SOUTHBOUND	5.0	14	70.0	7.8
RAMP A (STA. 20+41.60)	5.0	16	80.0	8.9
RAMP B (STA. 1+48.24)	5.0	16	80.0	8.9
WOODS ROAD (STA. 121+61)	5.8	68	394.4	43.8
STA. 123+24.79	5.0	26	130.0	14.4
<b>TOTALS =</b>			1,194.4	132.7

IL 267 SHORT TERM PAVEMENT MARKING / WORK ZONE PAVEMENT MARKING REMOVAL		
APPLICATIONS	SHORT TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL
	70300100	70301000
	WHITE (FOOT)	(4" LINE WIDTH) (SQUARE FOOT)
FIRST APPLICATION	185	0.0
SECOND APPLICATION	185	62.0
<b>OVERALL TOTALS =</b>	370	62

IL 267 PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 8"		
LOCATION OF PAVEMENT MARKING	MARKING TYPE	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 8"
		78004240 (FOOT)
<b>IL 267</b>		
RAMP A	WRONG WAY ARROW	36.0
<b>TOTALS =</b>		36.0

CONCRETE CURB REPAIR		
LOCATIONS		CONCRETE CURB REPAIR
		Z0012500 (FOOT)
<b>SANGAMON COUNTY</b>		
LOCATION #1, WALNUT ST., SPRINGFIELD	VARIOUS LOCATIONS AS DETERMINED BY THE ENGINEER	90.0
<b>MORGAN COUNTY</b>		
LOCATION #3, IL 267, SOUTH JACKSONVILLE	VARIOUS LOCATIONS AS DETERMINED BY THE ENGINEER	80.0
<b>TOTALS =</b>		170.0

IL 267 PAVEMENT PATCHING				
LOCATIONS		PAVEMENT PATCHING, TYPE II, 11 INCH	PAVEMENT PATCHING, TYPE III, 11 INCH	PAVEMENT PATCHING, TYPE IV, 11 INCH
		44200132 (SQ YD)	44200136 (SQ YD)	44200138 (SQ YD)
<b>MORGAN COUNTY</b>				
LOCATION #3, IL 267, SOUTH JACKSONVILLE	VARIOUS LOCATIONS AS DETERMINED BY THE ENGINEER	65.0	80.0	95.0
<b>TOTALS =</b>		65.0	80.0	95.0

**NOTE:**  
FOR LOCATIONS OF VARIOUS ITEMS PROPOSED FOR LOCATION #1, SEE SHEET 11, BILL OF MATERIALS.  
FOR LOCATIONS OF VARIOUS ITEMS PROPOSED FOR LOCATION #2, SEE SHEET 12, BILL OF MATERIALS.