GENERAL NOTES

- ACTUAL SIZE AND LOCATIONS OF ADDITIONAL PATCHES, OTHER THAN THOSE NOTED IN THE PLANS, WILL BE DETERMINED IN THE FIELD BY THE RESIDENT ENGINEER.
- 2. IN ADDITION TO FIELD SURVEYS AND AERIAL SURVEYS, PLAN DIMENSIONS AND DETAILS RELATIVE TO THE EXISTING FACILITIES HAVE BEEN TAKEN FROM EXISTING PLANS AND ARE SUBJECT TO CONSTRUCTION VARIATIONS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY SUCH DIMENSIONS AND DETAILS IN THE FIELD. SUCH VARIATIONS SHALL NOT BE A CAUSE FOR ADDITIONAL COMPENSATION, HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE BID UNIT PRICE FOR THE WORK.
- 3. WHERE SECTION OR SUBSECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL MONUMENTS UNTIL AN AUTHORIZED SURVEYOR OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR HAVING AN AUTHORIZED SURVEYOR REESTABLISH ANY SECTION OR SUBSECTION MONUMENTS DESTROYED BY HIS OPERATIONS.
- 4. ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER LISTED ON THE INDEX OF SHEETS OR THE COPY OF THE STANDARD INCLUDED IN THESE PLANS.
- 5. ALL DISTURBED AREAS WITHIN THE R.O.W. AND EASEMENTS SHALL BE SEEDED, FERTILIZED AND MULCHED, AS DIRECTED BY THE ENGINEER. SEEDING SHALL BE ACCORDING TO THE APPLICABLE ARTICLES OF SECTION 250 OF THE STANDARD SPECIFICATIONS. SEEDING SHALL NOT BE PERMITTED AT ANY TIME WHEN THE GROUND IS FROZEN, WET, OR IN AN UNTILLABLE CONDITION.

COMMITMENTS

 THE RESIDENT ENGINEER SHALL CONTACT STUDIES & PLANS CONCERNING ANY MAJOR PLAN CHANGE. TO MAKE SURE NO PREVIOUS COMMITMENTS (NOT LISTED) WERE MADE AFFECTING THE DESIGN AND ALLOW AN IMPROVED DESIGN FOR FUTURE PROJECTS. THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE FOR THIS PROJECT:

MIXTURE USE(S):	PATCHING			
PG:	PG 64-22			
DESIGN AIR VOIDS:	4.0% a N 70			
MIXTURE COMPOSITION: (GRADATION MIXTURE)	IL 19.0			
FRICTION AGGREGATE:	N/ A			
QUALITY MANAGEMENT	QC/QA			

	DISTRICT S	SIX		
EXAMINED form. OPERATIONS EN	APRIL CWeyony GINER	gend)	20 <u>14</u>	
EXAMINED AF	RILJII		20 14	
PROJECT INPLEM	MENTATION I	ENGINE	ER	耳
EXAMINED	April OPMENT EN	8	20 /4	

FILE NAME *	USER NAME · shimkusft	DESIGNED -	REVISED -				GFNI	ERAL NOT	TES		F.A.P.	SECTION	COUNTY	TOTA	AL SHE	ĒŦ
ci\pw_work\pwidot\shimkusft\d8387577\06	ZH83-sht-gannote,dgn	DRAWN -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	FAP 67/34 (IL 97)				**		MASON	6				
	PLOT SCALE * 100,0000 ' / in.	CHECKED -	REVISED -		FAP 0//34 (IL 97)							CONTRAC	CT NO.	72H0	13	
Defoult	PLOT DATE = Apr-11-2014 10:15:20AM	DATE -	REVISED -		SCALE:	SHEET	0F	SHEETS	STA.	TO STA.		FLLINOIS FED	. AID PROJECT			_
	* 		^		- OC CODING ON DEDAIG 2014-4											