



EAST PRAIRIE ST.

137

PAY ITEM	UNIT	QUADRANT
		SW
SIDEWALK REMOVAL	SQ FT	171.0
COMB. CONC. CURB & GUTTER REMOVAL	FT	19.0
COMB. CONC. CURB & GUTTER, TYPE B-6. 24	FT	19.0
PCC SIDEWALK 4"	SQ FT	188.0
DETECTABLE WARNINGS	SQ FT	10.0
HANDHOLE TO BE ADJUSTED	EA	1.0

NOTES:

1. SEE STANDARD 424011 FOR ADDITIONAL INFORMATION.
2. REMOVAL LIMITS ARE TO EXISTING JOINTS.
3. THE COST OF SIDE CURB SHALL BE INCLUDED IN PCC SIDEWALK 4".

→ DRAINAGE FLOW ARROW

LANDING AREA - 4' X 4' MIN. 5' X 5' TYPICAL
MAX 2.0%, 1.56% IS PREFERRED SLOPE IN ALL DIRECTIONS

FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -
c:\pw\work\p\dot\steffenmk\d0187107\074475-shit-sidewalk-details.dgn		DRAWN -	REVISED -
Default	PLOT SCALE = 15.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 4/4/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIDEWALK DETAILS
EAST PRAIRIE STREET

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
712	128RS-4,148K/RS-2	Macon	73	46
CONTRACT NO. 74475				
ILLINOIS FED. AID PROJECT				