

DECORATIVE AND NAVIGATION LIGHTING REPAIR SCHEDULE								
ID. NO.	NO. Item Location Action		Action					
-	Decorative Lighting	Spans 9-11	Remove decorative lighting wire, junction boxes and mounting bracket - See sheet S13					
33	Navigation Lighting	Spans 9-11	Replace navigation light assembly with LED light assembly - See sheet S13					
34	Navigation Lighting	Span 10	Install proposed LED assembly, mounting bracket, conduit, retro-reflective panel and access platform with ladder					
35	Navigation Lighting	Span 10	Install access ladder to upper white lights					

CONSTRUCTION SEQUENCE:

- 1. Remove the upper chord and lower chord decorative lights including drop boxes, equipment enclosures, mounts and mounting hardware, flexible cables, wires and conduits. The conduits should be checked to ensure that they do not carry wires for other bridge lights.
- 2. Remove 10 existing red or green navigation light assemblies.
- 3. Properly mount all proposed LED navigation light assemblies to existing mounts, modifying existing mounts only as needed to keep at same mounting height.
- 4. Any supporting equipment that is no longer needed shall be removed.
- 5. Replace white navigation light assemblies. a. Remove 3 existing white navigation light assemblies
 - and replace with LED navigation light assemblies. b. Verify location of existing white navigation light mounting brackets and adjust as necessary to meet current requirements. Replace conduit and mounting brackets as required, to meet vertical location requirements.
 - 1. The first light to be mounted between 10-15ft
 - above the green light.
 - 2. The white lights to be mounted 7-15ft apart.
- 6. Add new hardware at PP 21 for the mounting of the proposed red LED navigation light assembly. Install 4' x 4' red retro reflective panel which conforms to current USCG requirements to proposed North and South navigation light access platforms.



	USER NAME =	DESIGNED - AMM	REVISED	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL PLAN AND ELEVATION – LIGHTING REPAIRS	F.A.P.	SECTION	COUNTY TOTAL SHEET
		CHECKED - JGS	REVISED		S.N. 082–6001 MLK BRIDGE OVER MISSISSIPPI RIVER	799	1BR, DRS-2	ST. CLAIR 156 30
MODJESKI	PLOT SCALE =	DRAWN - AMM	REVISED					CONTRACT NO. 76B03
Experience great bridges.	PLOT DATE = 05/02/2014	CHECKED - JGS	REVISED		SHEET NO. S12 OF S138 SHEETS	ILLINOIS FED. AID PROJECT		D. AID PROJECT