

Springfield, Illinois

PLOT DATE = 05/02/2014

CHECKED - LMS

REVISED -

<u>GENERAL NOTES</u>

DESIGN: Current (at time of letting) AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires and Traffic Signals (Fatigue Category II - natural wind gust

CONSTRUCTION: Current (at time of letting) Illinois Department of Transportation Standard Specifications for Road and Bridge Construction, Supplemental Specifications and Recurring Special Provisions. ("Standard Specifications") All references to "Mast Arm Assembly and Pole" are applicable, unless otherwise noted.

WELDING: All welds to be continuous unless otherwise shown. All welding to be done in accordance with current AWS D1.1 Structural Welding Code and the Standard Specifications.

ANCHOR RODS: Shall conform to ASTM F1554 Grade 105. No welding shall be permitted

FASTENERS: All connection bolts shall be High Strength Bolts MI64, Galvanize M232 (A153), Type 3, or stainless steel heavy hex conforming to ASTM A193, Grade B8 or B8M, Class 1. U-bolts shall be produced from ASTM A276 Type 304, 304L, 316 or 316L, Condition A, cold finished, or an equivalent material acceptable to the Engineer. Nuts for stainless steel bolts shall be stainless steel conforming to ASTM A194, Grade 8 (AISI Type 304) or Grade 8F (AISI Type 303). All nuts shall be "locknuts" with nylon or steel inserts and semifinished hexagonal heads equivalent to the finished heavy hex series of the American National Standard. Washers for stainless steel bolts shall be stainless steel conforming to ASTM A240, Type 302 or 304.

REINFORCEMENT BARS: Reinforcement Bars designated (E) shall be epoxy coated in accordance with the Standard Specifications.

CAMBER: Minimum AASHTO camber = L / 1000 + dead load camber

STON STRUCTURE DATA TABLE									
	Station	€ to € Poles	Elevation A	Dimension D	Actual Sign/Signal Area				
	35+04.26	44′-6 ³ 4″	469,58	2′-3 ³ 8″	81				

SIGN STRUCTURE DATA TABLE

BILL OF MATERIAL

ITEM	UNIT	TOTAL
GN STRUCTURE MONOTUBE DUAL	Foot	45

IN STRUCTURE		SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
VER MISSISSIPPI RIVER	799	1BR, DRS-2	ST. CLAIR	156	151		
		CONTRACT NO. 76B03					
S138 SHEETS	ILLINOIS FED. AID PROJECT						