



Notes:

Existing reinforcement bars extending into the removal area shall be cleaned, straightened (if required) and incorporated into the new construction. Any reinforcement bars that are damaged during concrete removal shall be replaced with an approved bar splicer or anchorage system. Cost included with Concrete Superstructure.

No construction vehicles, live load, or construction equipment will be permitted on the deck area south of Beam 2 or north of Beam 6 and 5 feet east and west from the opening until requirements of the Standard Specifications Articles 503.20 and 1020.04 are met.

Contractor must take care and verify location of existing conduit in parapet before concrete removal.

Existing Conduit embedded in parapets shall remain in place and functional throughout construction. Provide temporary support during construction. Cost included with Concrete Removal.

Plan dimensions and details relative to existing plans are subject to nominal construction variations. The Contractor shall field verify existing dimensions and details affecting new construction and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in scope of the work, however, the Contractor will be paid for the quantity actually furnished at the unit price bid for the work.

LEGEND

Concrete Removal

DESIGNED - RPW REVISED -USER NAME = **CONCRETE REMOV** LIN ENGINEERING, LTD. FILE NAME = STATE OF ILLINOIS CHECKED - LMS REVISED -Consulting Engineers S.N. 082-6001 MLK BRIDGE 0 PLOT SCALE = DRAWN – AJF REVISED **DEPARTMENT OF TRANSPORTATION** Springfield, Illinois REVISED -SHEET NO. S134 OF PLOT DATE = 05/02/2014 CHECKED - LMS

CONCRETE REMOVAL PLAN

(South Parapet Shown, North Parapet Similiar)

VAL DETAILS	F.A.P. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
OVER MISSISSIPPI RIVER	799	1BR, DRS-2	ST. CLAIR	156	152
			CONTRACT	NO. 7	6B03
S138 SHEETS	ILLINOIS FED. AID PROJECT				