

PATCHING SCHEDULE

LOCATION				CLASS A PATCHES TYPE II, 8 INCH	CLASS A PATCHES TYPE IV, 8 INCH	CLASS A PATCHES TYPE II, 15 INCH	CLASS A PATCHES TYPE III, 15 INCH	CLASS A PATCHES TYPE IV, 15 INCH	CLASS A PATCHES TYPE II, 20 INCH	CLASS A PATCHES TYPE III, 20 INCH	CLASS D PATCHES TYPE I, 8 INCH	CLASS D PATCHES TYPE I, 15 INCH	CLASS D PATCHES TYPE I, 20 INCH	PATCHING REINFORCEMENT	TIE BARS 3/4"	SAW CUTS	* FRENCH DRAINS	* GEOTECHNICAL FABRIC FOR FRENCH DRAINS	AGGREGATE WEDGE SHOULDER, TYPE B	** PAINT PAVEMENT MARKING - LINE 4"	*** RAISED REFLECTIVE PAVEMENT MARKER	
DESCRIPTION	LENGTH (FT)	WIDTH (FT)	LANE	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	EACH	FOOT	CU YD	SQ YD	TON	WHITE FOOT	YELLOW FOOT	EACH
EB UNDER IL 158	7.0	12.0	DRIVING	9.3										9.3		69.0				10.0		
EB UNDER IL 158	67.0	12.0	DRIVING		89.3									89.3	34	249.0				20.0		2
EB UNDER IL 158	67.0	12.0	EXIT		89.3									89.3	34	182.0				87.0		
EB UNDER IL 158	21.0	12.0	DRIVING		28.0									28.0	11	111.0				10.0		
EB UNDER IL 158	21.0	12.0	EXIT		28.0									28.0	11	90.0				31.0		
WB UNDER IL 158	143.0	12.0	DRIVING		190.7									190.7	72	477.0				30.0		6
WB UNDER IL 158	143.0	12.0	EXIT		190.7									190.7	72	334.0				173.0		
WB UNDER IL 158	28.0	12.0	PASSING		37.3									37.3	14	104.0				10.0	28.0	1
EB UNDER COUNTY LINE RD	6.0	12.0	DRIVING						8.0					8.0		60.0				16.0		
EB UNDER COUNTY LINE RD	13.0	12.0	DRIVING							17.3				17.3		74.0				23.0		
EB UNDER COUNTY LINE RD	4.0	10.0	SHOULDER										4.4				2.2	17.6	0.5			
EB UNDER COUNTY LINE RD	6.0	12.0	DRIVING						8.0					8.0		60.0				16.0		
EB UNDER IL 160	4.0	10.0	SHOULDER										4.4				2.2	17.6	0.4			
EB UNDER IL 160	146.0	12.0	DRIVING					194.7						194.7	73	340.0				176.0		6
EB UNDER IL 160	4.0	10.0	SHOULDER										4.4				2.2	17.6	0.4			
EB UNDER BILLHARTZ RD	4.0	10.0	SHOULDER										4.4				2.2	17.6	0.4			
EB UNDER BILLHARTZ RD	71.0	12.0	DRIVING					94.7						94.7	36	190.0				91.0		2
EB UNDER BILLHARTZ RD	23.0	12.0	DRIVING					30.7						30.7	12	94.0				33.0		
WB UNDER BILLHARTZ RD	4.0	10.0	SHOULDER										4.4				2.2	17.6	0.4			
WB UNDER BILLHARTZ RD	215.0	12.0	DRIVING					286.7						286.7	108	478.0				255.0		10
WB UNDER BILLHARTZ RD	25.0	12.0	PASSING					33.3						33.3	13	98.0				10.0	25.0	1
WB UNDER BILLHARTZ RD	15.0	12.0	PASSING				20.0							20.0		78.0				10.0	15.0	
WB UNDER BILLHARTZ RD	4.0	10.0	SHOULDER										4.4				2.2	17.6	0.4			
EB UNDER ALBERS RD	38.0	12.0	DRIVING					50.7						50.7	19	124.0				48.0		1
EB UNDER ALBERS RD	4.0	10.0	SHOULDER										4.4				2.2	17.6	0.4			
EB UNDER ADDIEVILLE RD	28.0	12.0	DRIVING		37.3									37.3	14	104.0				38.0		1
EB UNDER ADDIEVILLE RD	20.0	12.0	DRIVING		26.7									26.7	10	88.0				30.0		
EB UNDER ADDIEVILLE RD	4.0	10.0	SHOULDER										4.4				2.2	17.6	0.2			
EB UNDER COVINGTON RD	52.0	12.0	DRIVING					69.3						69.3	26	152.0				62.0		2
EB UNDER COVINGTON RD	4.0	10.0	SHOULDER										4.4				2.2	17.6	0.4			
EB UNDER COVINGTON RD	10.0	12.0	DRIVING				13.3							13.3		68.0				20.0		
EB UNDER COVINGTON RD	10.0	12.0	DRIVING				13.3							13.3		68.0				20.0		
WB UNDER COVINGTON RD	151.0	12.0	DRIVING					201.3						201.3	76	350.0				181.0		6
EB UNDER IL 127	10.0	12.0	DRIVING				13.3							13.3		68.0				20.0		
EB UNDER IL 127	13.0	12.0	DRIVING				17.3							17.3		74.0				23.0		
EB UNDER IL 127	33.0	12.0	DRIVING					44.0						44.0	17	114.0				43.0		1
WB UNDER IL 127	60.0	12.0	DRIVING					80.0						80.0	30	168.0				80.0		2
TOTAL				9.3	717.3	40.0	37.3	1,085.3	16.0	17.3	4.4	31.1	4.4	1,922.7	682	4,466.0	20.0	158.0	3.4	1,566.0	68.0	41
USE				10	718	40	38	1,086	16	18	5	32	5	1,923	682	4,466	20	158	4	1,634		41

*NOTE: QUANTITIES WERE CALCULATED FOR FRENCH DRAINS ASSUMING A 12" MINIMUM THICKNESS
 **NOTE: QUANTITIES WERE CALCULATED FOR PAVEMENT MARKING ASSUMING THE LENGTH OF ENTIRE PATCH FOR SOLID OUTSIDE LANE LINES PLUS AN ADDITIONAL 10 FT OF SKIP-DASH FOR PATCHES 0-60 FT IN LENGTH, 20 FT FOR 60-120 FT, 30 FT FOR 120-180, AND 40 FT FOR 180-240 FT
 ***NOTE: QUANTITIES WERE CALCULATED FOR REFLECTIVE MARKERS ASSUMING 1 EACH FOR PATCHES 25-40 FT IN LENGTH, 2 EACH FOR 40-80 FT, 4 EACH FOR 80-120 FT, 6 EACH FOR 120-160 FT, 8 EACH FOR 160-200 FT, AND 10 EACH FOR 200-240 FT