LIST OF STANDARDS

000001-06 STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS DECIMAL OF AN INCH AND OF A FOOT 001006 442201-03 CLASS C AND D PATCHES 701201-04 LANE CLOSURE, 2L, 2W, DAY ONLY, FOR SPEEDS > 45 MPH 701301-04 LANE CLOSURE, 2L. 2W, SHORT TIME OPERATIONS 701311-03 LANE CLOSURE, 2L, 2W, MOVING OPERATIONS - DAY ONLY 701336-06 LANE CLOSURE, 2L. 2W, WORK AREAS IN SERIES, FOR SPEEDS > 45 MPH LANE CLOSURE, MULTILANE, DAY OPERATIONS ONLY, FOR SPEEDS > 45 MPH TO 55 MPH LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPER., FOR SPEEDS >45 MPH 701421-06 701426-06 701501-06 URBAN LANE CLOSURE. 2L. 2W, UNDIVIDED URBAN LANE CLOSURE. MULTILANE INTERSECTION 701701-09 701901-03 TRAFFIC CONTROL DEVICES TYPICAL PAVEMENT MARKINGS 780001-04 TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS 781001-03

GENERAL NOTE

- 1. THE STANDARDS AND REVISION NUMBERS LISTED IN THE LIST OF STANDARDS SHALL APPLY TO THIS PROJECT.
- 2. ILLINDIS STATE LAW REQUIRES A 48 HOUR NOTICE TO BE GIVEN TO ALL UTILITIES WITHIN THE PROJECT LIMITS BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. OR FOR NON MEMBERS THE UTILITY COMPANY DIRECTLY.
- 3. UTILITY INTERFERENCES ARE NOT ANTICIPATED ON THIS CONTRACT. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE HIS CONSTRUCTION ACTIVITIES WITH THE VARIOUS UTILITY OWNERRS. ALL POTENTIAL CONFLICTS SHALL BE INVESTIGATED AND REMEDIAL ACTION TAKEN PRIOR TO INTERRUPTION OF THE CONTRACTOR'S PROGRESS. NO ADDITIONAL COST SHALL BE ADDED TO THE CONTRACT RESULTING FROM UTILITY CONFLICTS.
- 4. FLAGGERS SHALL BE REQUIRED AT ALL TIMES DURING PATCHING OPERATIONS.
- 5. ALL PATCHING LOCATIONS ARE APPROXIMATE AND ARE TO BE LOCATED AS DIRECTED BY THE RESIDENT ENGINEERS.
- 6. THE CONTRACTOR AND THE ENGINEER SHALL BE AWARE THAT NO SURVEY WAS PERFORMED FOR THIS PROJECT. THE LOCATION, TOPOGRAPHY, AND QUANTITIES SHOWN IN THE PLANS WERE CREATED USING MICROFILM AND FIELD MEASUREMENTS. ALL SHALL BE ASSUMED TO BE APPROXIMATE. THE CONTRACTOR SHALL VERIFY DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
- 7. THE DEPARTMENT STRONGLY ENCOURAGES THE PRIME CONTRACTOR AND THEIR APPROVED SUBCONTRACTORS
 TO HIRE MINORITY, WOMEN AND DISADVANTAGED INDIVIDUALS FROM ITS FEDERALLY FUNDED HIGHWAY
 CONSTRUCTION CAREERS TRAINING PROGRAM (HCCTP) TO HELPMEET WORKFORCE AND TRAINEE GOALS. THIS
 PROGRAM IS TRAINING MINORITIES, WOMEN AND DISADVANTAGED INDIVIDUALS IN HIGHWAY CONSTRUCTION-RELATED
 SKILLS, E.G., MATH FOR THE TRADES, JOB READINESS, TECHNICAL SKILLS COURSEWORK (CARPENTRY, CONCRETE FLATWORK,
 BLUEPRINT READING, SITE PLANS, SITE WORK, TOOLS USE, ETC.) AND OSHA 10 HOUR CERTIFICATION, TO PREPARE THEM
 FOR A CAREER IN THE HIGHWAY CONSTRUCTION TRADES. GRADUATES ARE WELL-TRAINED AND READY TO BECOME
 PRODUCTIVE ENTRY-LEVEL CONSTRUCTION WORKERS, CONTACT THE DISTRICT 8 EEO OFFICE AT 618-346-3360 AND/OR THE
 HCCTP COORDINATOR AT 618-874-6528 TO LEARN MORE ABOUT THE PROGRAM AND FOR ASSISTANCE IN MEETING WORKFORCE
 AND TRAINEF GOALS.

COMMITMENTS

NONE

INDEX OF SHEETS

1 COVER

INDEX OF SHEETS, GENERAL NOTES, LIST OF STANDARDS & MIXTURE REQUIREMENTS

SUMMARY OF QUANTITIES

LOCATION MAP

5-6 TYPICAL SECTIONS

7-12 SCHEDULE OF QUANTITIES

ROUTE	FAP793/692/690
SECTION	(31,37,32,39,5-1,12,45,86)1-1
COUNTY	Madison
CONTRACT	76H21

STATE OF ILLINOIS

DEPARTMENT OF TRANSPORTATION

SCALE

DESCRIPTION: |Patching US 40 from 1-55/70 to Highland/Lake Road 1L 160

	US 40	IL 160	IL 160
ADT (Construction Yr.)	14000	3000	6600
MUZ:	3.6	1.7	3,2
SU%:	5.9	2.8	8.0
20 YR, ESAL;	3.88	0.40	1.90

MIXTURE USE	PATCHING	PATCHING	PATCHING	
AC/PG	PG-64-22	PG-64-22	PG-64-22	
RAP X (MAX)	SEE SPEC	SEE SPEC	SEE SPEC	
DESIGN AIR VOIDS	4.0% to Ndes=90	4.0% 6 Ndes=90	4.0% & Ndes=90	
MIX COMPOSITION				
GRADATION MIXTURE	IL 19.0 FG	IL 19,0 FG	IL 19.0 FG	
FRICTION AGG	MIXTURE "B"	MIXTURE "B"	MIXTURE "B"	
QUALITY MGMT PROGRAM	QC/QA	QC/QA	OC/0A	

• FAP 793/690/692

1						
	FILE NAME :	USER NAME = nieveze	DESIGNED	-	GEL	REVISED -
	01\p+,40r\\puidot\nievese\dØ388125\d876h21-w	htrplandgn	DRAWN	-	L.AC	REVISED -
		PLOT SCALE * 100.0000 '/ in.	CHECKED	~	MDP	REVISED -
		PLOT DATE = 4/31/2014	DATE	-	3/20/2012	REVISED -