

CLASS A PAVEMENT PATCHING SCHEDULE (SUGAR CREEK TO PEEKS BRIDGE)

MILE POINT	LANE		CLASS A PATCHES				SAW CUTS FT	TIE BARS EACH	PATCHING REINFORCEMENT SQ YDS
	LTH.	WTH.	TY I- 8"	TY II- 8"	TY III- 8"	TY IV- 8"			
			SQ YDS	SQ YDS	SQ YDS	SQ YDS			
WB 5.534	12	12			16		73		16
WB 5.674	4	12		5			57		5
WB 5.698	4	12		5			57		5
WB 5.855	4	12		5			57		5
WB 6.036	4	12		5			57		5
WB 6.109	4	12		5			57		5
WB 6.232	4	12		5			57		5
WB 6.320	4	12		5			57		5
WB 6.389	4	12		5			57		5
WB 6.432	38	6				25	100	19	25
WB 6.471	4	12		5			57		5
WB 6.520	4	12		5			57		5
WB 6.810	4	12		5			57		5
WB 6.879	16	12			21		81		21
WB 6.924	4	12		5			57		5
WB 6.946	4	12		5			57		5
WB 6.984	4	12		5			57		5
WB 7.004	12	12			16		73		16
WB 7.028	38	6				25	101	19	25
WB 7.060	38	6				25	101	19	25
WB 7.080	5	10		6			51		6
WB 7.140	4	12		5			57		5
WB 7.330	4	12		5			57		5
WB 7.502	4	12		5			57		5
WB 7.685	4	12		5			57		5
WB 7.702	4	12		5			57		5
WB 7.738	4	12		5			57		5
WB 7.818	15	12			20		79		20
WB 7.823	6	12		8			61		8
WB 7.851	4	12		5			57		5
WB 7.915	4	12		5			57		5
EB 5.534	12	12			16		73		16
EB 5.576	18	12			24		85		24
EB 5.596	4	12		5			57		5
EB 5.601	4	12		5			57		5
EB 5.620	12	12			16		73		16
EB 5.683	4	12		5			57		5
EB 5.871	4	12		5			57		5
EB 5.887	4	12		5			57		5
EB 5.908	4	12		5			57		5
EB 5.964	4	12		5			57		5
EB 5.991	19	12				25	87		25
EB 6.003	13	12			17		75		17
EB 6.073	4	12		5			57		5
EB 6.087	19	12				25	87		25
EB 6.100	4	12		5			57		5
EB 6.122	19	12				25	87		25
EB 6.177	4	12		5			57		5
EB 6.191	19	12				25	87		25
EB 6.207	8	6		5			41		5
EB 6.282	6	12		8			61		8
EB 6.314	19	12				25	87		25
EB 6.321	14	12			19		77		19
EB 6.365	4	12		5			57		5
EB 6.382	19	12				25	87		25
EB 6.418	4	12		5			57		5
EB 6.432	4	12		5			57		5
EB 6.467	4	12		5			57		5
EB 6.480	8	6		5			41		5
SUBTOTAL THIS PAGE			0	224	165	228	3820	57	617

MILE POINT	LANE		CLASS A PATCHES				SAW CUTS FT	TIE BARS EACH	PATCHING REINFORCEMENT SQ YDS
	LTH.	WTH.	TY I- 8"	TY II- 8"	TY III- 8"	TY IV- 8"			
			SQ YDS	SQ YDS	SQ YDS	SQ YDS			
EB 6.504	4	12		5			57		5
EB 6.517	15	12			20		79		20
EB 6.522	4	12		5			57		5
EB 6.594	4	12		5			57		5
EB 6.652	4	12		5			57		5
EB 6.672	4	12		5			57		5
EB 6.753	4	12		5			57		5
EB 6.854	4	12		5			57		5
EB 6.860	4	12		5			57		5
EB 6.894	38	6				25	101	19	25
EB 6.924	8	6		5			41		5
EB 6.938	8	6		5			41		5
EB 6.955	6	6	4				37		4
EB 6.977	8	6		5			41		5
EB 7.085	38	6				25	101	19	25
EB 7.174	5	10		6			51		6
EB 7.199	19	12				25	87		25
EB 7.205	38	6				25	101	19	25
EB 7.244	4	12		5			57		5
EB 7.270	38	6				25	101	19	25
EB 7.278	4	12		5			57		5
EB 7.291	4	12		5			57		5
EB 7.299	6	6	4				37		4
EB 7.304	8	6		5			41		5
EB 7.357	8	6		5			41		5
EB 7.361	4	12		5			57		5
EB 7.369	38	6				25	101	19	25
EB 7.389	4	12		5			57		5
EB 7.398	4	12		5			57		5
EB 7.420	38	6				25	101	19	25
EB 7.431	4	12		5			57		5
EB 7.459	4	12		5			57		5
EB 7.555	4	12		5			57		5
EB 7.597	4	12		5			57		5
EB 7.687	15	12			20		79		20
EB 7.693	4	12		5			57		5
EB 7.699	4	12		5			57		5
EB 7.714	4	12		5			57		5
EB 7.728	4	12		5			57		5
EB 7.773	4	12		5			57		5
EB 7.851	4	12		5			57		5
EB 7.915	4	12		5			57		5
SUBTOTAL			8	166	40	177	2606	114	391
TOTAL			8	390	205	405	6426	171	1008

East Bridge Joint of Peeks Bridge = 5.483
 East Bridge Joint on Sugar Creek = 7.934