

IL-15 CLASS B PAVEMENT PATCHING SCHEDULE WESTBOUND

PATCH #	MILE	SHOULDER TYPE	LANE	LENGTH (FT)	LANE WIDTH (FT)	CLASS B PATCH TYPE II 11 " (SQ YD)	CLASS B PATCH TYPE III 11 " (SQ YD)	CLASS B PATCH TYPE III 15 " (SQ YD)	CLASS B PATCH TYPE IV 15 " (SQ YD)	DOWEL BARS 1 1/2 INCH (EACH)	TIE BARS (EACH)	PAVEMENT FABRIC (SQ YD)	SAWCUT (FT)
66	1.650	HMA	3	6.00	12.00	8.00				20			48.00
67	0.750	HMA	1	12.00	12.00		16.00			20		16.00	60.00
68	0.700	HMA	1	12.00	12.00		16.00			20		16.00	60.00
69	0.650	HMA	1	12.00	12.00		16.00			20		16.00	60.00
70	0.620	CONCRETE	2	12.00	12.00		16.00			20		16.00	72.00
71	0.620	HMA	3	6.00	12.00	8.00				20			48.00
72	0.600	HMA	1	12.00	12.00			16.00		20		16.00	60.00
73	0.600	CONCRETE	2	12.00	12.00		16.00			20		16.00	72.00
74	0.600	HMA	3	12.00	12.00		16.00			20		16.00	60.00
75	0.580	HMA	1	12.00	12.00			16.00		20		16.00	60.00
76	0.580	CONCRETE	2	12.00	12.00		16.00			20		16.00	72.00
77	0.580	HMA	3	12.00	12.00		16.00			20		16.00	60.00
78	0.550	HMA	1	12.00	12.00			16.00		20		16.00	60.00
79	0.540	CONCRETE	2	12.00	12.00		16.00			20		16.00	72.00
80	0.530	HMA	1	12.00	12.00			16.00		20		16.00	60.00
81	0.520	HMA	1	12.00	12.00			16.00		20		16.00	60.00
82	0.520	CONCRETE	2	12.00	12.00		16.00			20		16.00	72.00
83	0.510	HMA	1	12.00	12.00			16.00		20		16.00	60.00
84	0.500	HMA	1	12.00	12.00			16.00		20		16.00	60.00
85	0.490	HMA	1	12.00	12.00			16.00		20		16.00	60.00
86	0.480	HMA	1	12.00	12.00			16.00		20		16.00	60.00
87	0.470	CONCRETE	2	12.00	12.00		16.00			20		16.00	72.00
88	0.450	HMA	3	12.00	12.00		16.00			20		16.00	60.00
89	0.430	CONCRETE	2	12.00	12.00		16.00			20		16.00	72.00
90	0.430	HMA	3	12.00	12.00		16.00			20		16.00	60.00
91	0.410	HMA	1	12.00	12.00			16.00		20		16.00	60.00
92	0.410	CONCRETE	2	12.00	12.00		16.00			20		32.00	72.00
93	0.390	HMA	1	30.00	12.00				40.00	20	14	40.00	96.00
94	0.390	HMA	3	12.00	12.00		16.00			20		16.00	60.00
95	0.350	CONCRETE	2	6.00	12.00	8.00				20			54.00
96	0.300	HMA	1	12.00	12.00			16.00		20		16.00	60.00
97	0.300	CONCRETE	2	12.00	12.00		16.00			20		16.00	72.00
98	0.150	HMA	1	12.00	12.00			16.00		20		16.00	60.00
99	0.150	CONCRETE	2	12.00	12.00		16.00			20		16.00	72.00
100	0.120	HMA	1	12.00	12.00			16.00		20		16.00	60.00
101	0.100	HMA	1	12.00	12.00			16.00		20		16.00	60.00
102	0.050	HMA	1	12.00	12.00			16.00		20		16.00	60.00
103	0.050	CONCRETE	2	12.00	12.00		16.00			20		16.00	72.00
104	0.000	HMA	1	12.00	12.00			16.00		20		16.00	60.00
105	0.000	CONCRETE	2	12.00	12.00		16.00			20		16.00	72.00
SUBTOTAL:						24.00	320.00	256.00	40.00	800	14	632.00	2550.00
ANTICIPATED FAILURES (15%):						3.60	48.00	38.40	6.00	120	3	94.80	382.50
TOTAL:						27.60	368.00	294.40	46.00	920.00	17.00	726.80	2932.50

NOTE: LANE 1 = LEFT LANE
LANE 2 = MIDDLE LANE
LANE 3 = RIGHT LANE

* FAP 103674

FILE NAME =	USER NAME = lagemannge	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
et:\pw\work\p\dot\lagemannge\10388138\0876H25-sht-plan.dgn	DRAWN -	REVISED -	*					29-I-1, (31,410,410-1)I-1	ST. CLAIR	17	13	
PLOT SCALE = 100.0000' / 1in.	CHECKED -	REVISED -	CONTRACT NO. 76H25									
PLOT DATE = 4/15/2014	DATE -	REVISED -	SCALE:					SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	