

IL ROUTE 15 PAINT PAVEMENT MARKING-LINE 4" SCHEDULE						
PATCH NUMBER EASTBOUND	MILE MARKER	LENGTH	4" WHITE SKIP DASH	4" SOLID WHITE	4" SOLID YELLOW	RAISED REFLECTIVE PAVEMENT MARKER
		FOOT	FOOT	FOOT	FOOT	EACH
1	0.000	12.00	3.00		12.00	1.00
2	0.000	12.00	6.00			1.00
3	0.030	30.00	7.50		30.00	1.00
4	0.050	12.00	3.00		12.00	1.00
5	0.050	12.00	6.00			1.00
6	0.100	12.00	3.00		12.00	1.00
7	0.100	12.00	6.00			1.00
8	0.140	12.00	3.00		12.00	1.00
9	0.140	12.00	6.00			1.00
10	0.200	12.00	6.00			1.00
11	0.220	12.00	3.00		12.00	1.00
12	0.220	12.00	6.00			1.00
13	0.240	8.00	2.00		8.00	1.00
14	0.240	8.00	4.00			1.00
15	0.260	50.00	25.00			1.00
16	0.300	12.00	3.00		12.00	1.00
17	0.300	12.00	3.00	12.00		1.00
18	0.340	12.00	3.00		12.00	1.00
19	0.340	12.00	3.00		12.00	1.00
20	0.340	12.00	3.00	12.00		1.00
21	0.400	8.00	2.00		8.00	1.00
22	0.500	6.00	3.00			1.00
23	0.600	12.00	3.00		12.00	1.00
24	0.600	12.00	6.00			1.00
25	0.600	6.00	1.50	6.00		1.00
26	0.620	12.00	6.00			1.00
27	0.630	12.00	6.00			1.00
28	0.640	12.00	6.00			1.00
29	0.670	30.00	15.00			1.00
30	0.700	12.00	6.00			1.00
31	0.700	12.00	3.00	12.00		1.00
32	0.800	12.00	6.00			1.00
33	1.000	12.00	3.00		12.00	1.00
34	1.000	12.00	6.00			1.00
35	1.050	12.00	6.00			1.00
36	1.100	12.00	6.00			1.00
37	1.200	12.00	6.00			1.00
38	1.300	12.00	6.00			1.00
39	1.310	8.00	4.00			1.00
40	1.320	8.00	4.00			1.00
41	1.330	50.00	25.00			1.00
42	1.350	12.00	6.00			1.00
43	1.370	12.00	6.00			1.00
44	1.400	12.00	6.00			1.00
45	1.450	12.00	6.00			1.00
46	1.450	12.00	3.00	12.00		1.00
47	1.500	8.00	4.00			1.00
48	1.500	6.00	1.50	6.00		1.00
49	1.510	12.00	6.00			1.00
50	1.520	12.00	6.00			1.00
51	1.530	6.00	3.00			1.00
52	1.540	12.00	6.00			1.00
53	1.550	6.00	3.00			1.00
54	1.550	6.00	1.50	6.00		1.00
55	1.580	6.00	3.00			1.00
56	1.590	12.00	6.00			1.00
57	1.600	6.00	3.00			1.00
58	1.630	12.00	3.00		12.00	1.00
59	1.630	12.00	6.00			1.00
60	1.630	12.00	3.00	12.00		1.00
61	1.650	12.00	6.00			1.00
62	1.650	12.00	3.00	12.00		1.00
63	1.670	12.00	3.00	12.00		1.00
64	1.670	12.00	6.00			1.00
65	1.670	8.00	2.00	8.00		1.00
SUBTOTALS			336.00	110.00	178.00	65.00

IL ROUTE 15 PAINT PAVEMENT MARKING-LINE 4" SCHEDULE						
PATCH # WESTBOUND	MILE MARK	LENGTH	4" WHITE SKIP DASH	4" SOLID WHITE	4" SOLID YELLOW	RAISED REFLECTIVE PAVEMENT MARKER
		FOOT	FOOT	FOOT	FOOT	EACH
66	1.650	6.00	1.50	6.00		1.00
67	0.750	12.00	3.00		12.00	1.00
68	0.700	12.00	3.00		12.00	1.00
69	0.650	12.00	3.00		12.00	1.00
70	0.620	12.00	6.00			1.00
71	0.620	6.00	1.50		6.00	1.00
72	0.600	12.00	3.00		12.00	1.00
73	0.600	12.00	6.00			1.00
74	0.600	12.00	3.00	12.00		1.00
75	0.580	12.00	3.00		12.00	1.00
76	0.580	12.00	6.00			1.00
77	0.580	12.00	3.00		12.00	1.00
78	0.550	12.00	3.00		12.00	1.00
79	0.540	12.00	6.00			1.00
80	0.530	12.00	3.00		12.00	1.00
81	0.520	12.00	3.00		12.00	1.00
82	0.520	12.00	6.00			1.00
83	0.510	12.00	3.00		12.00	1.00
84	0.500	12.00	3.00		12.00	1.00
85	0.490	12.00	3.00		12.00	1.00
86	0.480	12.00	3.00		12.00	1.00
87	0.470	12.00	6.00			1.00
88	0.450	12.00	3.00		12.00	1.00
89	0.430	12.00	6.00			1.00
90	0.430	12.00	3.00		12.00	1.00
91	0.410	12.00	3.00		12.00	1.00
92	0.410	12.00	6.00			1.00
93	0.390	30.00	7.50	30.00		1.00
94	0.390	12.00	3.00	12.00		1.00
95	0.350	6.00	3.00			1.00
96	0.300	12.00	3.00		12.00	1.00
97	0.300	12.00	6.00			1.00
98	0.150	12.00	3.00	12.00		1.00
99	0.150	12.00	6.00			1.00
100	0.120	12.00	3.00		12.00	1.00
101	0.100	12.00	3.00		12.00	1.00
102	0.050	12.00	3.00		12.00	1.00
103	0.050	12.00	6.00			1.00
104	0.000	12.00	3.00	12.00		1.00
105	0.000	12.00	6.00			1.00
SUBTOTAL			157.50	84.00	246.00	40.00
TOTAL			493.50	194.00	424.00	105.00
TOTAL				1,112		105

IL-158 / IL-15 TOTAL QUANTITIES PATCHING										
PARTIAL DEPTH REMOVAL TYPE I, 2"	PARTIAL DEPTH REMOVAL TYPE II, 2"	PARTIAL DEPTH REMOVAL TYPE III, 2"	PARTIAL DEPTH REMOVAL TYPE IV, 2"	PARTIAL DEPTH PATCHING	LONGITUDINAL PARTIAL DEPTH REMOVAL, 2"	LONGITUDINAL PARTIAL DEPTH PATCHING, 2"	CLASS B PATCH TYPE II, 11"	CLASS B PATCH TYPE III, 11"	CLASS B PATCH TYPE IV, 11"	PATCHING REINFORCEMENT
SQ YD	SQ YD	SQ YD	SQ YD	TONS	FOOT	TONS	SQ YD	SQ YD	SQ YD	(SQ YD)
87.14	639.91	69.00	529.00	149.48	1549.05	39.10	119.60	409.40	621.00	594.93

DOWEL BARS 1 1/2 INCH	TIE BARS 3/4"	PAVEMENT FABRIC	SAW CUTS	CLASS B PATCH TYPE III, 15"	CLASS B PATCH TYPE IV, 15"	CLASS A PATCH TYPE I, 11"	CLASS A PATCH TYPE II, 11"	CLASS A PATCH TYPE III, 11"	CLASS A PATCH TYPE IV, 11"
EACH	EACH	SQ YD	FT	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD
1311.00	274.00	1389.20	8797.50	294.40	46.00	87.40	404.80	64.40	38.33

IL-158 / IL-15 TOTAL QUANTITIES PAVEMENT MARKING				
4" WHITE SKIP DASH PAV. MARKING	4" SOLID WHITE PAINT PAV. MARKING	4" SOLID YELLOW PAINT PAV. MARKING	4" WHITE SKIP DASH THERMOPLASTIC PAVEMENT MARKING	RAISED REFLECTIVE PAVEMENT MARKER
FOOT	FOOT	FOOT	FOOT	EACH
799.00	3096.00	913.00	543.00	211.00
5351.00				211.00

NOTE: LANE 1 = LEFT LANE
LANE 2 = MIDDLE LANE
LANE 3 = RIGHT LANE

FILE NAME =	USER NAME = lagemannge	DESIGNED -	REVISED -
et:\pwork\pwork\dot\lagemannge\10388138\0876H25-shr-plan.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / 1in.	CHECKED -	REVISED -
	PLOT DATE = 4/15/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES		
SCALE:	SHEET NO. OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	29-I-1, (31,410,410-1)I-1	ST. CLAIR	17	17
CONTRACT NO. 76H25				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

* FAP 103674