

SUMMARY OF QUANTITIES				CONSTRUCTION CODE	
				COUNTY	CONSTRUCTION CODE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	WILLIAMSON	80% FEDERAL 20% STATE
				ROADWAY	URBAN
31100700	SUBBASE GRANULAR MATERIAL, TYPE A 8"	SO YD	1665	1665	
35501320	HOT-MIX ASPHALT BASE COURSE, 9"	SO YD	318	318	
35501332	HOT-MIX ASPHALT BASE COURSE, 12"	SO YD	1419	1419	
40200500	AGGREGATE SURFACE COURSE, TYPE A 6"	SO YD	252	252	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	929	929	
40600300	AGGREGATE (PRIME COAT)	TON	16	16	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	73	73	
40600990	TEMPORARY RAMP	SO YD	32	32	
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	214	214	
42001300	PROTECTIVE COAT	SO YD	51	51	
44000100	PAVEMENT REMOVAL	SO YD	650	650	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	833	833	
44004250	PAVED SHOULDER REMOVAL	SO YD	219	219	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1346	1346	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	536	536	

FILE NAME =	USER NAME = #USER*	DESIGNED -	REVISED -
d:\work\p101dot\kell\gk\d0374978\784	22-ntaropr_ssq_index.dgn	DRAWN -	REVISED -
	PLOT SCALE = 1/8" = 1' / 1/4"	CHECKED -	REVISED -
	PLOT DATE = 3/22/2014	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
726	(1-2) N-3	WILLIAMSON	50	6
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 78402	