

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	LOCATION: URBAN			
			ROUTE: FAP 322 (US 51)			
			FUNDING:	80% FED	20% STATE	80% FED 20% LOCAL
TOTAL QUANTITY	ROADWAY 0005	ROADWAY 0005	ROADWAY 0005	ROADWAY 0005		
40600909	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-9.5FG, N90	TON	1155	1101	54	
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	399	399		
40600990	TEMPORARY RAMP	SQ YD	1878	1878		
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	2185	2009	176	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	28	28		
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	15202	13823	1379	
44200966	CLASS B PATCHES, TYPE I, 10 INCH	SQ YD	69	69		
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	337	337		
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	334	334		
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	356	356		
44201299	DOWEL BARS 1 1/2"	EACH	1798	1798		
44213100	PAVEMENT FABRIC	SQ YD	690	690		
44213200	SAW CUTS	FOOT	5163	5163		
44213204	TIE BARS 3/4"	EACH	426	426		

14