

MODEL: SOQ-1 [Sheet]
FILE NAME: c:\pw_work\pwitd\jammal.aramahi@illinois.gov\093124\ID103524-shr-SOQ.dgn

				CONSTRUCTION CODE	
				100% STATE	100% STATE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	ROADWAY
				0005	0005
				URBAN	URBAN
20200100	EARTH EXCAVATION	CU YD	5,792	5,792	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	580	580	
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	632	632	
30300112	AGGREGATE SUBGRADE IMPROVEMENT, 12"	SQ YD	9,477	9,477	
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	21,324	21,324	
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	28,526	28,526	
40600370	LONGITUDINAL JOINT SEALANT	FOOT	13,668	13,668	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	127	127	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	133	133	
40602985	HOT-MIX ASPHALT BINDER COURSE, IL-9.5, N70	TON	4,734	4,734	
40604062	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N70	TON	4,143	4,143	
44000100	PAVEMENT REMOVAL	SQ YD	2,764	2,764	2
44000164	HOT-MIX ASPHALT SURFACE REMOVAL, 3 3/4"	SQ YD	42,260	42,260	
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	317	317	
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	20	20	

* SPECIALTY ITEM

2 REVISED SHEET 6/2/2025

	USER NAME = jammal.aramahi	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	F.A.P. ROUTE 335 (IL 176) SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -					335	FAP 0335 23 SMART2	MCHENRY	25	3
		CHECKED -	REVISED -					CONTRACT NO. 62V57				
	PLOT DATE = 3/20/2025	DATE -	REVISED -					ILLINOIS FED. AID PROJECT				
SCALE:		SHEET 1 OF 5 SHEETS		STA.		TO STA.						

MODEL: SOQ-2 [Sheet]
FILE NAME: c:\pw_work\pwitd\jammal.aramahi\illinois.gov\093124\ID103524-shr-SOQ.dgn

				CONSTRUCTION CODE	
				100% STATE	100% STATE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	ROADWAY
				0005	0005
				URBAN	URBAN
44201796	CLASS D PATHCES, TYPE IV, 12 INCH	SQ YD	223	223	
44213200	SAW CUTS	FOOT	23,856	23,856	
48203037	HOT-MIX ASPHALT SHOULDERS, 10"	SQ YD	9,477	9,477	
60920024	PIPE CULVERTS TO BE CLEANED 24"	FOOT	300	300	
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	125	125	
63200310	GUARDRAIL REMOVAL	FOOT	125	125	
64200108	SHOULDER RUMBLE STRIPS, 8 INCH	FOOT	24,793	24,793	
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	5,792	5,792	
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	2	2	
* 66901001	REGULATED SUBSTANCES PRE-CONSTRUCTION PLAN	L SUM	1	1	
* 66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	L SUM	1	1	
* 66901006	REGULATED SUBSTANCES MONITORING	CAL DA	4	4	
67100100	MOBILIZATION	L SUM	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	

* SPECIALTY ITEM

 REVISED SHEET 6/2/2025

	USER NAME = jammal.aramahi	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	F.A.P. ROUTE 335 (IL 176) SUMMARY OF QUANTITIES			F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -					335	FAP 0335 23 SMART2	MCHENRY	25	4
		CHECKED -	REVISED -					CONTRACT NO. 62V57				
	PLOT DATE = 3/20/2025	DATE -	REVISED -					ILLINOIS FED. AID PROJECT				
SCALE:		SHEET 2 OF 5 SHEETS		STA.		TO STA.						