

MODEL: SOQ-1 [Sheet]
FILE NAME: c:\pwwork\widnicholas.babu@illinois.gov\dl1052107\105125-sht-SOQ.dgn

SUMMARY OF QUANTITIES					TYPE CODE					
					URBAN	URBAN	URBAN	URBAN	URBAN	URBAN
					ROADWAY	SIGNAL	SIGNAL PAGE AVE	ROADWAY	EVP SIDEWALK	INTER-CONNECT
					100% STATE	100% STATE	93.3% STATE 6.7% ELGIN	100% STATE	100% ELGIN	100% STATE
	Code No.	Item	Unit	Total Quantity	0005	0021	0021	0005	0021	0021
	20200100	EARTH EXCAVATION	CU YD	255	255					
	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	32	32					
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1174	1174					
	25200110	SODDING, SALT TOLERANT	SQ YD	1174	1174					
	25200200	SUPPLEMENTAL WATERING	UNIT	17.6	17.6					
	30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	11	11					
	30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	128	128					
	35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	112	112					
	35600728	HOT-MIX ASPHALT BASE COURSE WIDENING, 13"	SQ YD	128	128					
	40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	287	287					
	40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	21978	21978					
	40600370	LONGITUDINAL JOINT SEALANT	FOOT	13739	13739					
	40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	49	49					
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	421	421					
	40603090	HOT-MIX ASPHALT BINDER COURSE, IL-9.5, N90	TON	2273	2273					
	40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	1536	1536					
	40604060	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N50	TON	13	13					
	40604062	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N70	TON	3012	3012					
	42001300	PROTECTIVE COAT	SQ YD	2356	2356					
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	14235	14235					
	42400800	DETECTABLE WARNINGS	SQ FT	684	684					
* = SPECIALTY ITEM										
		USER NAME = nicholas.babul	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION					
			DRAWN -	REVISED -						
			CHECKED -	REVISED -						
		PLOT DATE = 3/5/2025	DATE -	REVISED -						

SUMMARY OF QUANTITIES					TYPE CODE					
					URBAN	URBAN	URBAN	URBAN	URBAN	URBAN
					ROADWAY	SIGNAL	SIGNAL PAGE AVE	ROADWAY	EVP SIDEWALK	INTER-CONNECT
					100% STATE	100% STATE	93.3% STATE 6.7% ELGIN	100% STATE	100% ELGIN	100% STATE
	Code No.	Item	Unit	Total Quantity	0005	0021	0021	0005	0021	0021
	44000100	PAVEMENT REMOVAL	SQ YD	209	209				1	
	44000164	HOT-MIX ASPHALT SURFACE REMOVAL, 3 3/4"	SQ YD	32474	32474					
	44000600	SIDEWALK REMOVAL	SQ FT	19165	14165				5000	
	44003100	MEDIAN REMOVAL	SQ FT	2524	2524					
	44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	2226	2226					
	44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	100	100					
	44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	500	500					
	44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	300	300					
	44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	250	250					
	60250200	CATCH BASINS TO BE ADJUSTED	EACH	5	5					
	60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	2	2					
	60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	5	5					
	60255500	MANHOLES TO BE ADJUSTED	EACH	2	2					
	60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	17	17					
	60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	5	5					
	60406001	FRAMES AND LIDS, TYPE 1, ADA COMPLIANT, OPEN LID	EACH	1	1					
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	220	220					
	60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	1442	1442					
	67100100	MOBILIZATION	L SUM	1	1					
*	66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	255	255					
*	66900530	SOIL DISPOSAL ANALYSIS	EACH	3	3					
*	66901001	REGULATED SUBSTANCES PRE-CONSTRUCTION PLAN	L SUM	1	1					
*	66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	L SUM	1	1					
*	66901006	REGULATED SUBSTANCES MONITORING	CAL DA	16	16					
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
	70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
	70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					
	70102634	TRAFFIC CONTROL AND PROTECTION, STANDARD 701611	L SUM	1	1					
* = SPECIALTY ITEM										
					1 REVISED SHEET 6/2/2025					
ILLINOIS TRANSPORTATION		SUMMARY OF QUANTITIES IL 25 (DUNDEE AVE.) [S/O I-90 TO PAGE AVE.]			F.A.P RTE.	SECTION		COUNTY	TOTAL SHEETS	SHEET NO.
					360	2024-1017-RS		KANE	77	3
					CONTRACT NO. 62X59					
SCALE:		SHEET 1	OF 3	SHEETS	STA.	TO STA.		ILLINOIS FED. AID PROJECT		

MODEL - SQQ-2 [Sheet]
FILE NAME - c:\pwwork\jwiddon\nicholas.babul\illinois.gov\td1052105125-sht-SQQ.dgn

SUMMARY OF QUANTITIES					TYPE CODE					
					URBAN	URBAN	URBAN	URBAN	URBAN	URBAN
					ROADWAY	SIGNAL	SIGNAL PAGE AVE.	ROADWAY	EVP SIDEWALK	INTER-CONNECT
					100% STATE	100% STATE	93.3% STATE 6.7% ELGIN	100% STATE	100% ELGIN	100% STATE
	Code No.	Item	Unit	Total Quantity	0005	0021	0021	0005	0021	0021
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1					
	70300100	SHORT TERM PAVEMENT MARKING	FOOT	23370	23370					
	70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	9747	9747					
	70300211	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS - PAINT	SQ FT	1548	1548					
	70300221	TEMPORARY PAVEMENT MARKING - LINE 4" - PAINT	FOOT	27321	27321					
	70300241	TEMPORARY PAVEMENT MARKING - LINE 6" - PAINT	FOOT	2952	2952					
	70300251	TEMPORARY PAVEMENT MARKING - LINE 8" - PAINT	FOOT	1443	1443					
	70300261	TEMPORARY PAVEMENT MARKING - LINE 12" - PAINT	FOOT	7161	7161					
	70300281	TEMPORARY PAVEMENT MARKING - LINE 24" - PAINT	FOOT	1536	1536					
	70307120	TEMPORARY PAVEMENT MARKING - LINE 4" - TYPE IV TAPE	FOOT	5843	5843					
*	72000100	SIGN PANEL - TYPE 1	SQ FT	25			25			
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	516	516					
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	9107	9107					
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	984	984					
*	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	481	481					
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2387	2387					
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	512	512					
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	380	380					
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	380	380					
	78300202	PAVEMENT MARKING REMOVAL - WATER BLASTING	SQ FT	7775	7775					
*	81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	4835		1340	96			3399
* = SPECIALTY ITEM										
		USER NAME = nicholas.babul	DESIGNED -		REVISED -		STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION			
			DRAWN -		REVISED -					
			CHECKED -		REVISED -					
		PLOT DATE = 3/4/2025	DATE -		REVISED -					

SUMMARY OF QUANTITIES					TYPE CODE					
					URBAN	URBAN	URBAN	URBAN	URBAN	URBAN
					ROADWAY	SIGNAL	SIGNAL PAGE AVE.	ROADWAY	EVP SIDEWALK	INTER-CONNECT
					100% STATE	100% STATE	93.3% STATE 6.7% ELGIN	100% STATE	100% ELGIN	100% STATE
	Code No.	Item	Unit	Total Quantity	0005	0021	0021	0005	0021	0021
*	81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	174		22	152			
*	81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	347		155	192			
*	81400100	HANDHOLE	EACH	15		6	3			6
*	81400200	HEAVY-DUTY HANDHOLE	EACH	1		1				
*	81400300	DOUBLE HANDHOLE	EACH	1			1			
*	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	4		3	1			
*										
*	87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	4870						4870
*	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	2994		2415	579			
*	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	3550		1853	578		1119	
*	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2274		1301	801			
*	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	200		200				
*	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	4083		3780	303			
*	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	87			87			
*	87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	1355		897	458			
*	87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	4		1	3			
*	87700110	STEEL MAST ARM ASSEMBLY AND POLE, 14 FT.	EACH	1			1			
*	87700120	STEEL MAST ARM ASSEMBLY AND POLE, 16 FT.	EACH	1			1			
*	87700160	STEEL MAST ARM ASSEMBLY AND POLE, 24 FT.	EACH	1			1			
*	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	20		4	16			
*	87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4			4			
* = SPECIALTY ITEM  REVISED SHEET 6/2/2025										
ILLINOIS TRANSPORTATION		SUMMARY OF QUANTITIES IL 25 (DUNDEE AVE.) [S/O I-90 TO PAGE AVE.]			F.A.P RTE.	SECTION		COUNTY	TOTAL SHEETS	SHEET NO.
					360	2024-1017-RS		KANE	77	4
					CONTRACT NO. 62X59					
SCALE:		SHEET 2 OF 3 SHEETS STA.			TO STA.		ILLINOIS FED. AID PROJECT			

MODEL: SOQ-3 [Sheet]
FILE NAME: c:\pw work\pwidth\nicholas.babul@illinois.gov\d1052107\D105125-sht-SOQ.dgn

REV-SEP