



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 2nd, 2025

SUBJECT FAP Route 845 (IL 154)
Project BR-STP-ED18(378)
Section 112(RS-4,BLP-1);112B-4
Franklin County
Contract No. 78786

Item No. 225, June 13th, 2025 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised Schedule of Prices.
2. Revised pages 2-3 of the Special Provisions.
3. Revised sheets 14 and 33 of the plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

UTILITIES

Effective 1984

Revised 2/15/23

Add the following after the first paragraph of Article 105.07:

Underground utilities have been plotted from available surveys and records and, therefore, their locations must be considered approximate only. There also may be utilities for which the locations are unknown. Verification of locations of underground utilities, shown or not shown, will be the responsibility of the Contractor. The following utility companies have facilities within the project limits which may require adjustment:

Status of JULIE Member Utilities
78786 IL 154 Bridge Replacement and Bike Path, Franklin County

1

Name and Address of Utility	Type	Location	Estimated Adjustment Status
Ameren Illinois 1800 W Main St Marion, IL 62959 ATTN: Rob Estes Phone: (618) 998-4560 Email: restes@ameren.com	Electric	Throughout	Relocation To Begin Sept 1 st And Completed By Sept 30 th Due To Summer Lock Out Of Transmission Lines. Only Effect Area Around The Northside Of Structure #028-0052
Ameren Illinois 1800 West Main St Marion, IL 62959 ATTN: Traven Watts Tel: (618) 998-4504 Cell: (618) 351-8440 Email: TWatts2@Ameren.com	Gas	Throughout	Before Or During Construction
Ewing / INA Water Commission 104 West Main Whittington, IL 62897 ATTN: Adam Allsop Tel: (618) 629-2221 Cell: (618) 927-6756 Email: ewingina@gmail.com	Water	Throughout	Before Or During Construction
Frontier Communications 208 West Union St. Marion, IL 62959 ATTN: Rick Shaw Tel: (618) 997-0253 Cell: (618) 967-5540 Email: rick.shaw@ftr.com	Telephone/ Fiber Optic	Throughout	Before Or During Construction

New Wave/Sparklight Communications 184 Southtowne Shopping Center Du Quoin, IL 62832 ATTN: Terry Delaval Tel: (618) 663-7300 Email: Terry.Delaval@sparklight.biz	Cable T.V.	Throughout	Before Or During Construction
Rend Lake Conservancy District 11231 Marcum Branch Rd. P.O. Box 907 Benton, IL 62812 ATTN: Beth Ponce Tel: (618) 439-4321 Cell: (618) 534-2328 Email: engr@rendlake.org	Water/ Sewer	Throughout	Before Or During Construction
Tri County Electric Co-Op. P.O. Box 369 Mt. Vernon, IL. 62864 ATTN: Danny Hopfinger Tel: (618) 244-5151 Cell: (618) 214-9980 Email: dhopfinger@tricountycoop.com	Electric	Throughout	None Anticipated

The above represents the best information the Department has available and is only included for the convenience of the bidder. The applicable provisions of Section 102 and Articles 105.07, 107.20, 107.37, 107.38, 107.39, 107.40, and 108.02 shall apply.

Above utility relocation information reflected as of 1/31/2025. Once the proposed right of way is clear and final plans are available, a notice will be sent to the utility companies instructing them to begin relocation of utilities in conflict with the project.

TRAFFIC CONTROL PLAN

Effective 1985

Revised 4/17/23

During the entire construction period, the road shall be kept open to traffic as follows:

- (a) The highway shall be kept open to at least one lane of traffic at all times, and to two lanes of traffic to the greatest extent possible.
- (b) Access to all public roads and private entrances shall be maintained during all stages of the work.
- (c) Over one lane of the existing or new bridge during construction of the opposite lane of the structure.

Prior to allowing traffic on any portion of the roadway that has been cold milled, the Contractor shall have erected "Rough Grooved Surface" and "Uneven Pavement" signs that conform to the details shown in the plans. A minimum of one sign at each end of the improvement will be required. The Contractor shall maintain the "Rough Grooved Surface" signs until the cold milled surface is covered with binder. The Contractor shall maintain the "Uneven Pavement" signs until