

PRICE FOR PAY ITEM "REMOVAL OF UNDERPASS LIGHTING UNIT, NO SALVAGE".

- 44 EA 400 WATT HPS LUMINAIRES ATTACHED TO CHANNEL
- 12 EA 250 WATT HPS LUMINAIRES ATTACHED TO CHANNEL
- 56 EA 10" X 8" X 6" STAINLESS STEEL JUNCTION BOXES ATTACHED TO STRUCTURE 1000 FT 1 ½" DIA. PVC COATED RGS CONDUIT ATTACHED TO CHANNEL
- 400 FT 1" DIA. PVC COATED RGS CONDUIT ATTACHED TO CHANNEL
- 350 FT ¾" DIA. LIQUID TIGHT FLEX CONDUIT
- 1800 FT 1/C #2, 600 VOLT CONDUCTOR IN 1 ½" CONDUIT
- 1500 FT 1/C #12, 600 VOLT CONDUCTOR IN 1" CONDUIT
- 1700 FT 1/C #10, 600 VOLT CONDUCTOR IN %" LIQUID TIGHT FLEX CONDUIT
- 1 LOT 1-5/8" STAINLESS STEEL CHANNEL AND FITTINGS ATTACHED TO STRUCTURE
- 2. EXISTING LIGHTING CONTROLLER AND FEEDS TO UNDERPASS LUMINAIRES TO BE USED FOR TEMPORARY UNDERPASS LIGHTING DURING CONSTRUCTION. REMOVE CONTROLLER, FOUNDATION AND FEEDS WHEN NEW PERMANENT UNDERPASS LIGHTING IS IN OPERATION.
- 3. REMOVE CIRCUIT CONDUCTORS AND ABANDON CONDUITS.
- 4. CONTRACTOR TO VERIFY LOCATIONS OF EXISTING CONDUITS FROM CONTROLLER TO UNDERPASS.

LEGEND



ALL LUMINAIRES, CONDUITS, MOUNTING MATERIALS, JUNCTION BOXES AND CONDUCTORS IN THIS AREA ARE TO BE REMOVED

SPAAN Tech, Inc. 311 S. Wacker Drive, Suite 2400 phone 312.277.8800 fm 312.277.800 wds www.5pamTech.com

COLLINS ENGINEERS

USER NAME = CDOT - City of Chicago	DESIGNED -	IAB	REVISED -
PLOT SCALE = 40.0000000 '/ in.	DRAWN -	DL/TM	REVISED -
PLOT DATE = 3/5/2013 8:54:01 AM	CHECKED -	YK	REVISED -
PLOT DRIVER= HDR - PDF.plt	DATE -	DEC 2012	REVISED -

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

I-90/94 AT OHIO STREET							F.A.I. RTE.		
							90/94	0303-474HB-R	
	SCALE: 1" = 20"	SHEET NO.	OF	SHEETS	STA.	TO STA.	FED. R	OAD DIST. NO. 1	ILLINOIS

368 163 COOK CONTRACT NO. 60F63