


TOLLWAY TRAFFIC CONTROL

TRAFFIC CONTROL ON INTERSTATE 88 AND AT RAMP TERMINALS SHALL BE IN ACCORDANCE WITH THE FOLLOWING ILLINOIS TOLLWAY STANDARDS:

- E1 CONSTRUCTION SIGNS
- E2 LANE CLOSURE DETAILS
- E3 SHOULDER CLOSURE DETAILS
- E4 MAINTENANCE OF TRAFFIC REVERSE CURVE
- E5 TEMPORARY GORE DETAILS

NOTES

- LOCATION OF TRAILER MOUNTED FULL MATRIX PORTABLE CHANGEABLE MESSAGE SIGN SHALL BE COORDINATED WITH THE ENGINEER AND THE ILLINOIS TOLLWAY. MESSAGE TO BE DISPLAYED WILL BE REMOTELY CONTROLLED BY THE ILLINOIS TOLLWAY TRAFFIC MANAGEMENT CENTER.
- 2. THE TRAILER MOUNTED FULL MATRIX PORTABLE CHANGEABLE MESSAGE SIGN SHALL REMAIN IN PLACE FOR THE ENTIRE DURATION OF THE CONTRACT. NO ADDITIONAL COMPENSATION WILL BE ALLOWED FOR DELAYS EXTENDING THE CONTRACT BEYOND COMPLETITION DATE AS SHOWN IN THE SPECIAL PROVISIONS.



FILE NAME *	USER NAME · \$USER\$	DESIGNED (2.50)	REVISED -
\$FILKE\$	**************************************	DRAWN KES	REVISED
	PLOI SCALE - ISCALEI	CHECKED JCM	REVISED
	POT DATE - MOSTER	DATE 10/15/2012	REVISED .

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

MAINTENANCE				Œ	OF TRAFFIC - STAG			STAGE	1				
		RAI	ИP	В	/	NTER	STA	ſΕ	88				
 SHEET	NO.	20	OF	118	SH	EETS	ST	٨.	8968400	70	STA.	6573+00	•

	HI INOIS FED. A	CONTRAC	NO. 6	0131
338	(112 & 113) WRS-5	DUPAGE	963	136
A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.