



SEE SHEET 14 OF 18
FOR CONTINUATION
MATCHLINE "J"

NOTES:

1. INSTALL 50A BREAKER IN LIGHTING CONTROLLER CABINET FOR POWER TO RELOCATED DMS. THE COST OF THIS WORK IS INCLUDED IN THE PRICE OF THE ITEM "DMS REMOVAL AND INSTALLATION."
2. REUSE EXISTING 5 KVA STEP DOWN TRANSFORMER INSIDE DMS CABINET. INSTALL NEW ETHERNET SWITCH AND FIBER OPTIC TERMINATION PANEL.
3. PROVIDE 3-1/C NO. 2 AND 1/C NO. 8 GROUND IN 3" RGC (POWER) AND 1-CAT 5E OUTDOOR RATED ETHERNET CABLE IN 3" RGC (COMMUNICATIONS) BETWEEN DMS CONTROLLER AND DMS. THIS WORK IS INCLUDED IN THE PRICE OF THE ITEM "DMS REMOVAL AND INSTALLATION."
4. FOUNDATION FOR 50 FT. CAMERA POLE SHALL BE PER DISTRICT ONE DETAIL BE-301 (REFER TO LIGHTING PLANS).

FILE NAME =	USER NAME = pscott	DESIGNED - JG	REVISED -
		DRAWN - PS	REVISED -
	PLOT SCALE = 50.000' / IN.	CHECKED - RS	REVISED -
	PLOT DATE = 3/29/2013	DATE - 3/29/13	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

ITS PLAN	
I-94 AT STONY ISLAND EXTENSION	
SCALE: 1"=50'	SHEET NO. 13 OF 18 SHEETS
STA.	TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	2012-059-BR	COOK	631	341
			CONTRACT NO. 60J12	
ILLINOIS FED. AID PROJECT				

ITS-14

S:\Projects\3810 Stony Island Feeder - BBA\Project Work\CADD Sheets\168J12-11-ITS-14.dwg