



NOTES

- REFER TO SPECIAL PROVISIONS FOR CABINET DETAILS AND ADDITIONAL REQUIREMENTS.
- CABINET ENTRIES INCLUDE VERTICAL ARRANGEMENT FOR MAJOR EQUIPMENT ITEMS ONLY.
- INSTALL ADDITIONAL ITEMS ON SIDE AND BACK PANELS PER THE SPECIAL PROVISIONS.
- THE CONTRACTOR SHALL INSTALL INSULATED BUSHINGS AND DUCT SEALANT AT ALL CONDUIT BEND TERMINATIONS IN FOUNDATIONS.
- CONCRETE BASE TO BE FORMED AT LEAST 6.0 IN ABOVE THE GROUND SURFACE.
- CONCRETE BASE MUST BE CAST IN PLACE.
- ALL WORK INDICATED SHALL BE PAID FOR UNDER ITEM CABINET, MODEL 334 EXCLUSIVE OF THE CONCRETE FOUNDATION.
- CABINET BOTTOM CONFIGURATION SHALL BE AS DIRECTED BY THE ENGINEER.

FILE NAME =	USER NAME = \$USER\$	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	FIBER OPTIC CABLE INSTALLATION CABINET, MODEL 334 DETAILS	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN -	REVISED -			94	2012-059-BR	COOK	631	374	
		CHECKED -	REVISED -			CONTRACT NO. 60J12					
		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					
				SCALE: 1"=50'	SHEET NO. 15 OF 16 SHEETS	STA.	TO STA.				