INDEX OF SHEETS

	SHEET NO.	DESCRIPTION
	i.	TITLE SHEET
	2	INDEX OF SHEETS, STATE STANDARDS, & GENERAL NOTES
	3-4	SUMMARY OF QUANTITIES
	5-14	BRIDGE REPAIR DETAILS - SN 022-0022
	15-18	TRAFFIC CONTROL PLANS (STAGE I & II)
	19	TRAFFIC STAGING PLAN
	-20	DETOUR DURING STACE-H
	21-22	FINAL PAVEMENT MARKING PLAN
	23	BUTT JOINT AND HMA TAPER DETAILS (BD-32)
Δ	24	FREEWAY-ENTRANCE AND-EXIT RAMP (TC 8)
	25	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS (TC-10)
	26	TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS. (SNOW-PLOW RESISTANT) (TC-11)
	27	TYPICAL PAVEMENT MARKING (TC-13)
	27A.	TRAFFIC CONTROL DETAILS
	~28	ARTERIAL ROAD INFORMATION SIGN (TC-22)
ΔC	284.	DRIVEWAY ENTRANCE SIGNING (TC-26)
	29	BRIDGE APPROACH SHOULDER PAVEMENT. STANDARD 2324-5

STATE STANDARDS

A (701101-03)

DESCRIPTION

701301-04 LANE CLOSURE, 2L, 2W SHORT TIME OPERATIONS

701421-08 LANE CLOSURE, MULTILANE, UNDIVIDED WITH GROS

701901 ~ *02*

TRAFFIC CONTROL DEVICES

DESIGNED -

CHECKED -

DRAWN

DATE

REVISED

REVISED

REVISED

REVISED

606001-05 606301-04 101426-05

USER NAME : ggrangeytab

PLOT SCALE . 100.0000 '/ 10

PLOT DATE . 12/14/2012

(623) i-sht-plen.don

GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT (800) 892-0123 OR 811 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE & GAS UTILITIES. (48 HOUR NOTIFICATION IS REQUIRED).

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND THE CITY OF WEST CHICAGO.

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARMENT.

BEFORE BEGINING ANY WORK, THE CONTRACTOR SHALL RETAIN AND RECORD FOR FUTURE REFERENCE. ALL EXISTING PAVEMENT MARKING LINES (AND RAISED REFLECTIVE PAVEMENT MARKERS) IN ORDER THAT THESE LOCATIONS CAN BE RE-ESTABLISHED FOR STRIPPING. EXACT LOCATIONS OF ALL PAVEMENT MARKINGS SHALL BE AS DIRECTED BY THE ENGINEER.

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.

THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL ARTERIAL SUPERVISOR AT (847)705-4470, A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

THE ENGINEER SHALL CONTACT DON CHIARUOI AREA TRAFFIC FIELD TECHNICIAN AT (847) 741-9857 A MINIMUM OF TWO (2) WEEKS PRIOR TO THE PLACEMENT OF PERMANENT PAVEMENT MARKINGS.

THESE PLANS HAVE BEEN PREPARED FROM NOTES RECEIVED FROM THE BUREAU OF MAINTENANCE.

THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECT.

DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS.

ALL DAMAGE TO EXISTING PAVEMENT MARKINGS OR RAISED REFLACTIVE PAVEMENT MARKERS OUTSIDE THE REMOVAL LINE SHOWN ON THE PLANS SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE.

CONCRETE SUPERSTRUCTURE SHALL HAVE A SEVEN DAY MINIMUM CURE.

THE DEPARTMENT HAS DETERMINED THAT IN STREAM WORK IS NOT REQURED FOR THE WORK SPECIFIED IN THIS CONTRACT. THE DEPARTMENT HAS NOT OBTAINED A 404 PERMIT. IF THE CONTRACTOR CHOOSES TO USE ACTIVITIES REQUIRING AN USACE 404 PERMIT IT IS THE CONTRACTOR'S RESPONSIBILITY TO SECURE THE PROPER USACE PERMITS.

A Rev. 6-3-13

Rey,

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCALE:

SHEET OF SHEETS
STATE STANDARDS, GENERAL NOTES

STATE STANDARDS, GENERAL NOTES

F.A.P. RTE. SECTION COUNTY TOTAL SHEETS NO.

2011-067-1 DUPAGE SHEETS NO.

CONTRACT NO. 60P86

SCALE: SHEET OF SHEETS STA. TO STA. | ILLINOIS|FED. AID PROJECT

FILE NAME :