INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	TITLE SHEET
2	INDEX OF SHEETS, STATE STANDARDS, & GENERAL NOTES
3-4	SUMMARY OF QUANTITIES
5-14	BRIDGE REPAIR DETAILS - SN 022-0022
15-18	TRAFFIC CONTROL PLANS (STAGE I & II)
19	TRAFFIC STAGING PLAN
-20	DETOUR DURING STAGE II
21-22	FINAL PAVEMENT MARKING PLAN
23	BUTT JOINT AND HMA TAPER DETAILS (BD-32)
24	FREEWAY ENTRANCE AND EXIT RAMP (TC-8)
25	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS. INTERSECTIONS, AND DRIVEWAYS (TC-10)
26	TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT) (TC-11)
27	TYPICAL PAVEMENT MARKING (TC-13)
27A.	TRAFFIC CONTROL DETAILS
28	ARTERIAL ROAD INFORMATION SIGN (TC-22)
29	BRIDGE APPROACH SHOULDER PAVEMENT, STANDARD 2324-5

STATE STANDARDS

STANDARD NO.

DESCRIPTION

701301 - 04 LANE CLOSURE, 2L, 2W SHORT TIME OPERATIONS

701431-08 LANE CLOSURE, MULTILANE, UNDIVIDED WITH CROSSOVER, FOR SPEEDS & 45 MPH TO 55 MPH

701606*-08*

URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN

701901 - *02*

TRAFFIC CONTROL DEVICES

606001-05

GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT (800) 892-0123 OR 811 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE & GAS UTILITIES, (48 HOUR NOTIFICATION IS REQUIRED).

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND THE CITY OF WEST CHICAGO.

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARMENT.

BEFORE BEGINING ANY WORK, THE CONTRACTOR SHALL RETAIN AND RECORD FOR FUTURE REFERENCE.
ALL EXISTING PAVEMENT MARKING LINES (AND RAISED REFLECTIVE PAVEMENT MARKERS) IN ORDER
THAT THESE LOCATIONS CAN BE RE-ESTABLISHED FOR STRIPPING. EXACT LOCATIONS OF ALL PAVEMENT
MARKINGS SHALL BE AS DIRECTED BY THE ENGINEER.

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.

THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL ARTERIAL SUPERVISOR AT (847)705-4470, A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

THE ENGINEER SHALL CONTACT DON CHIARUOI AREA TRAFFIC FIELD TECHNICIAN AT (847) 741-9857 A MINIMUM OF TWO (2) WEEKS PRIOR TO THE PLACEMENT OF PERMANENT PAVEMENT MARKINGS.

THESE PLANS HAVE BEEN PREPARED FROM NOTES RECEIVED FROM THE BUREAU OF MAINTENANCE.

THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECT.

DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS.

ALL DAMAGE TO EXISTING PAVEMENT MARKINGS OR RAISED REFLACTIVE PAVEMENT MARKERS OUTSIDE THE REMOVAL LINE SHOWN ON THE PLANS SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE.

CONCRETE SUPERSTRUCTURE SHALL HAVE A SEVEN DAY MINIMUM CURE.

THE DEPARTMENT HAS DETERMINED THAT IN STREAM WORK IS NOT REQURED FOR THE WORK SPECIFIED IN THIS CONTRACT. THE DEPARTMENT HAS NOT OBTAINED A 404 PERMIT. IF THE CONTRACTOR CHOOSES TO USE ACTIVITIES REQUIRING AN USACE 404 PERMIT IT IS THE CONTRACTOR'S RESPONSIBILITY TO SECURE THE PROPER USACE PERMITS.

				·										Rey	
FILE NAME :	USER NAME : gorengestab	DESIGNED -	REVISEO -		INDEX OF SHEETS STATE STANDARDS, GENERAL NOTES						F.A.P.	SECTION	COUNTY	TOTAL SHEETS	SHEET
ci\p+.work\p+idot\gor#ng&utab\d8273151\0	162311-sht-plan.dgm	DRAWN -	REVISED ~	STATE OF ILLINOIS							347	2011-067-1	DUPAGE	29	-10.
	PLDT SCALE * 100.0000 '/)n,	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION								2011 007 1	CONTRACT NO)P86
	PLOT DATE + 12/14/2012	DATE -	REVISED -		SCALEI	SHEET	QF	SHEETS	STA,	TO STA.		[LLINGIS FE	O. AID PROJECT		