SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 100% STATE ROADWAY					
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	10	10					
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	5	5					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	475	475					
25200110	SODDING, SALT TOLERANT	SQ YD	475	475					
25200200	SUPPLEMENTAL WATERING	UNIT	4.8	4.8					
35501304	HOT-MIX ASPHALT BASE COURSE, 5"	SQ YD	94	94					
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	32	32					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	147	147					
40600300	AGGREGATE (PRIME COAT)	TON	736	736					
40600400	MIXTURE FOR CRACKS, JOINTS,	TON	276	276					
	AND FLANGEWAYS								
40600827	POLYMERIZED LEVELING BINDER (MACHINE	TON	7588	7588					
	METHOD), IL-4.75, N50								
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT	SQ YD	1587	1587					
	JOINT								
40601005	HOT-MIX ASPHALT REPLACEMENT OVER	TON	466	466					
	PATCHES								

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 100% STATE ROADWAY					
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX	TON	3.6	3.6					
	"D", N50								
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE	TON	18028	18028					
	COURSE, MIX "F", N90								
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	20	20					
42001300	PROTECTIVE COAT	SQ YD	4144	4144					
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY	SQ YD	274	274					
	PAVEMENT, 8 INCH								
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	2750	2750					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	183958	183958					
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	306	306					
44000600	SIDEWALK REMOVAL	SQ FT	2750	2750					
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	2078	2078					
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	60	60					
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	1200	1200					
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	567	567					

FILE NAME = c:\pw_work\pw1dot\bradusth\d282900\D94212-Designation	USER NAME = bradusth	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 4/11/2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

WESTERN AVENUE (34TH STREET TO COLUMBUS DRIVE)
SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
370	2011-089-RS	COOK	30	3
		CONTRACT NO. 60R16		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT