





SANDBAG COFFERDAM

A sandbag cofferdam should be installed by hand during lowflow conditions in order to isolate the streambank stabilization work from the flows of Salt Creek. If at the time of construction the contractor believes that a cofferdam is not necessary to perform the work, the contractor shall gain approval from the Corps to proceed without installing a cofferdam. An impermeable liner such as visqueen (minimum 40 ml thick) shall be placed in the creek and the sandbags which also must be constructed of an impermeable material shall be stacked in an alternating pattern upon the liner. The liner shall be placed such that it may be wrapped over the sandbags towards the shore to create a seal. Sandbag cofferdam should be installed in a C-Shape design along the portion of the streambank requiring restoration. Following cofferdam installation, a pump equipped with a sediment bag will be used to dewater the area between the cofferdam and the streambank (see detail). The dewatering bag shall be placed as far from the creek as possible to maximize the time for sediment removal. The pump must be floated on top of the water to minimize the intake of sediment. The cofferdam and pump must be maintained as necessary to allow the contractor to work "in the dry" and to control sediment. Following completion of the streambank restoration work, the sandbag cofferdam will be removed by hand starting with the downstream side in order to not impede water flows. Stabilization of upland areas may be required following removal of the sediment bag filter pad and should be completed using the specified native seed mix.

In no case shall the sandbag cofferdam be installed for greater than 30 days.

FILE NAME =	USER NAME = prozeton	DESIGNED - JA	REVISED -			E.A.U. RTE	SECTION COUNTY TOTAL SHEET
%\30.2.180%2490w\$\%826383126\0.vr}%8E?;38066383126;2L3+3		DRAWN - POR	REVISED -	STATE OF ILLINOIS	CARRIAGE WAY DRIVE	10-0	00101-00-BR COOK 34 16
	PLOT SCALE = 20'	CHECKED JGS	REVISED -	DEPARTMENT OF TRANSPORTATION	CONSTRUCTION DETAILS	CONTRACT NO. 63787	
	PLOT DATE = 2/12/2013	DATE - 11/3C/12	REVISED -		SCALE: N.T.S. SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT

N.T.S.