

SUMMARY OF QUANTITIES

SPECIAL PROVISIONS SPECIALTY ITEMS	CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	FEDERAL - 80% STATE - 10% CITY - 10%				
					ROADWAY	TRAFFIC SIGNAL	TRAINEES	CITY - 100%	
								EMERGENCY VEHICLE PREEMPTION	TREES
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	134	0004	0021	0042	0021	0031
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	88	88				
	20101200	TREE ROOT PRUNING	EACH	4	4				
A	20200100	EARTH EXCAVATION	CU YD	2,560	2,560				
	20200200	ROCK EXCAVATION	CU YD	100	100				
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	280	280				
	20800150	TRENCH BACKFILL	CU YD	120	120				
	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	550	550				
*	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	2,155	2,155				
	21301072	EXPLORATION TRENCH 72" DEPTH	FOOT	250	250				
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	27	27				
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	27	27				
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	27	27				
*	25200110	SODDING, SALT TOLERANT	SQ YD	2,155	2,155				
*	25200200	SUPPLEMENTAL WATERING	UNIT	97	97				
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	45	45				
	28000400	PERIMETER EROSION BARRIER	FOOT	1,130	1,130				
	28000510	INLET FILTERS	EACH	24	24				
A	30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	280	280				
A	30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	2,741	2,741				
	35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	572	572				
	35101700	AGGREGATE BASE COURSE, TYPE B 5"	SQ YD	268	268				
	35501305	HOT-MIX ASPHALT BASE COURSE, 5 1/4"	SQ YD	462	462				
	35501307	HOT-MIX ASPHALT BASE COURSE, 5 3/4"	SQ YD	114	114				
	35501318	HOT-MIX ASPHALT BASE COURSE, 6 1/2"	SQ YD	1,314	1,314				
A	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	190	190				
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,779	1,779				
	40800300	AGGREGATE (PRIME COAT)	TON	14	14				
	40800635	LEVELING BINDER (MACHINE METHOD), N70	TON	280	290				
	40800882	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	115	115				
	40803340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	795	795				
	42001300	PROTECTIVE COAT	SQ YD	1,341	1,341				
	42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	257	257				
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	2,810	2,810				
	42400400	PORTLAND CEMENT CONCRETE SIDEWALK 7 INCH	SQ FT	605	605				
	42400800	DETECTABLE WARNINGS	SQ FT	230	230				
	44000100	PAVEMENT REMOVAL	SQ YD	708	708				
	44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	450	450				
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	848	848				
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2,617	2,617				
	44000600	SIDEWALK REMOVAL	SQ FT	4,750	4,750				
	44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	23	23				
	44201773	CLASS D PATCHES, TYPE I, 11 INCH	SQ YD	10	10				
	44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	12	12				

SPECIALTY ITEM
A SPECIAL PROVISION

SPECIAL PROVISIONS SPECIALTY ITEMS	CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	FEDERAL - 80% STATE - 10% CITY - 10%			CITY - 100%		
					ROADWAY	TRAFFIC SIGNAL	TRAINEES	EMERGENCY VEHICLE PREEMPTION	TREES	
	44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SQ YD	188	188					
	44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	2,478	2,478					
Δ	50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	13	13					
	550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	108	108					
	550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	70	70					
	550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	182	182					
	550A2330	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 15"	FOOT	100	100					
	550A2360	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 24"	FOOT	35	35					
	550B0050	STORM SEWERS, CLASS B, TYPE 1 12"	FOOT	52	52					
	550B0120	STORM SEWERS, CLASS B, TYPE 1 24"	FOOT	295	285					
	55100400	STORM SEWER REMOVAL 10"	FOOT	10	10					
	55100500	STORM SEWER REMOVAL 12"	FOOT	119	119					
	55100700	STORM SEWER REMOVAL 15"	FOOT	71	71					
	55101200	STORM SEWER REMOVAL 24"	FOOT	10	10					
Δ *	55400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	1	1					
	60107700	PIPE UNDERDRAINS 6"	FOOT	160	160					
	60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	12	12					
	60203040	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1	1					
	60206230	CATCH BASINS, TYPE C, TYPE 23 FRAME AND GRATE	EACH	1	1					
	60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	1	1					
	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1					
	60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3					
	60224039	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	3	3					
	60236625	INLETS, TYPE A, TYPE 11V FRAME AND GRATE	EACH	1	1					
	60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	4	4					
	60255500	MANHOLES TO BE ADJUSTED	EACH	3	3					
	60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	3	3					
	60258200	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2	2					
	60260100	INLETS TO BE ADJUSTED	EACH	1	1					
	60261320	INLETS TO BE ADJUSTED WITH NEW TYPE 11V FRAME AND GRATE	EACH	1	1					
	60261540	INLETS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	2	2					
	60263900	INLETS TO BE RECONSTRUCTED WITH NEW TYPE 11 FRAME AND GRATE	EACH	2	2					
	60264140	INLETS TO BE RECONSTRUCTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	1	1					
	60265700	VALVE VAULTS TO BE ADJUSTED	EACH	1	1					
	60265900	VALVE VAULTS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	4	4					
	60266100	VALVE VAULTS TO BE RECONSTRUCTED	EACH	2	2					
	60500040	REMOVING MANHOLES	EACH	2	2					
	60500050	REMOVING CATCH BASINS	EACH	1	1					
	60500090	REMOVING INLETS	EACH	12	12					
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	179	179					
	60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	125	125					
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	2,248	2,248					
Δ *	66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	175	175					
Δ *	66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1					

Printed: May 7, 2013 @ 8:15 AM By: Larry Nolan - Tab: 04 Sum of Quant 22-34

COPYRIGHT © 2013 ENGINEERING ENTERPRISES, INC.

Engineering Enterprises, Inc.
CONSULTING ENGINEERS
52 Wheeler Road
Sugar Grove, Illinois 60954
630.466.6700 / www.eeteeb.com

USER NAME = Larry Nolan

DESIGNED - JRL & SWM

DRAWN - CLN

CHECKED - JL

DATE - 11/13/12

REVIS

DESIGNED - JRL & SWM

DRAWN - CLN

CHECKED - JL

DATE - 11/13/12

REVIS

REVIS

REVISED - JPS 02/08/13

REVISED -

REVISED -

REVISED -

REVISED -

REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N.T.S.

SHEET NO. 1 OF 2 SHEETS

STA.

TO STA.

F.A.P.
RTE.
577

SECTION

10-00068-00-TL

COUNTY

WILL

TOTAL SHEETS

65

SHEET NO.

4

CONTRACT NO. 63788

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-90036(19)

Path: \\S05PR01\CD\Projects\10662\10662.DWG FINAL Dwg\10662-04.dwg