

SUMMARY OF QUANTITIES					
	ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	CONST. TYPE CODE (002)
	20101400	NITROGEN FERTILIZER NUTRIENT	LBS	3.6	
	20101500	PHOSPHORUS FERTILIZER NUTRIENT	LBS	3.6	
	20101600	POTASSIUM FERTILIZER NUTRIENT	LBS	3.6	
	20200100	EARTH EXCAVATION	CU YD	79.90	
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	35.15	
	21101601	TOPSOIL FURNISH AND PLACE, 1 INCH	SQ YD	201.0	
	25000100	SEEDING, CLASS-I	ACRE	0.04	
	25100105	MULCH, METHOD 1	ACRE	0.04	
	31102100	SUBBASE GRANULAR MATERIAL (CA-6), TYPE C, 4 INCH	SQ YD	502.0	
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	4518.0	
	42400800	DETECTABLE WARNINGS	SQ FT	60.0	
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	21.5	
	44000600	SIDEWALK REMOVAL	SQ FT	54.0	
	67100100	MOBILIZATION	L SUM	1.0	
Δ	78001150	PAINT PAVEMENT MARKING 12 INCH	FOOT	144.0	
	XX008200	STABILIZED DRIVEWAY PAVEMENT	SQ YD	8.0	

Δ SPECIALTY ITEMS

FILE NAME -	USER NAME -	DESIGNED - RAS	REVISED - MAS 1/14/13	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	SCALE: _____	SHEET NO. 2 OF 7 SHEETS	STA. _____ TO STA. _____	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN - RAS	REVISED - MAS 2/28/13							12-LU001-00-SW	WILL	7	2	
	PLOT SCALE = 1"=20'	CHECKED - TC	REVISED - _____							STA 0+00 TO STA 9+50 GREEN GARDEN PLACE				CONTRACT NO. 63820
	PLOT DATE =	DATE - 12/27/12	REVISED - _____							ILLINOIS FED. AID PROJECT				