

**SUMMARY OF QUANTITIES**

FUNDING SOURCE: SRTS - 100% FEDERAL				
	PAY ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT	CONST. TYPE CODE 0021
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	40
	25200110	SODDING, SALT TOLERANT	SQ YD	40
	25200200	SUPPLEMENTAL WATERING	UNIT	5
	31101180	SUBBASE GRANULAR MATERIAL, TYPE B 2"	SQ YD	20
	35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	45
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	12
	42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	250
	* 42400800	DETECTABLE WARNINGS	SQ FT	64
	44000100	PAVEMENT REMOVAL	SQ YD	50
	44000600	SIDEWALK REMOVAL	SQ FT	250
	60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	400
	67100100	MOBILIZATION	L SUM	1
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
#	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	150
#	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	238
#	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1946
#	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	50
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	35
	* Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	40
	* Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	1
#	* XX006651	MEDIAN SIGN SPECIAL	EACH	10

\* INDICATES SPECIAL PROVISION  
# INDICATES SPECIALTY ITEMS