

PLAN	SURVEYED	DATE
	PLOTTED	BY
	ALIGNED	CHECKED
	NOTE BOOK	NO.

PROFILE	SURVEYED	DATE
	PLOTTED	BY
	GRADES	CHECKED
	NOTE BOOK	NO.

SUMMARY OF QUANTITIES					CONSTRUCTION TYPE CODE
S.I.	CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	021
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	12	12
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	182	182
	20800150	TRENCH BACKFILL	CUYD	55	55
~	* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	4937	4937
~	* 21101695	TOPSOIL FURNISH AND PLACE, 30"	SQYD	70	70
~	* 25000100	SEEDING, CLASS 1	ACRE	1.02	1.02
	28000510	INLET FILTERS	EACH	15	15
~	35101598	AGGREGATE BASE COURSE, TYPE B 3"	SQ YD	1981	1981
	42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	34	34
~	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	14590	14590
~	42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	3241	3241
~	42400800	DETECTABLE WARNINGS	SQ FT	160	160
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ /D	762	762
	44000800	SIDEWALK REMOVAL	SQ FT	572	572
~	48101498	AGGREGATE SHOULDERS, TYPE B 4"	SQ YD	2274	2274
~	542D2737	PIPE CULVERTS, CLASS D, TYPE 4 12"	FOOT	270	270
	550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	125	125
	56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	24	24
	60206905	CATCH BASINS, TYPE C, TYPE 1 FRAME, OPEN LID	EACH	5	5
	60255500	MANHOLES TO BE ADJUSTED	EACH	2	2
	60260100	INLETS TO BE ADJUSTED	EACH	5	5
	60266600	VALVE BOXES TO BE ADJUSTED	EACH	3	3
	67100100	MOBILIZATION	L SUM	1	1

\* - INDICATES SPECIALTY ITEMS  
~ - INDICATES SPECIAL PROVISIONS

SUMMARY OF QUANTITIES					CONSTRUCTION TYPE CODE
S.I.	CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	021
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1082	1082
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	280	280
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	215	215
~	* 89502376	REBUILD EXISTING HANDHOLE	EACH	1	1
~	* B2001616	TREE, CRATAEGUS CRUSGALLI INERMIS (THORN LESS COCKSPUR HAWTHORN), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	7	7
~	X2020410	EARTH EXCAVATION (SPECIAL)	CU YD	856	856
~	XX008200	STABILIZED DRIVEWAY PAVEMENT	SQ YD	349	349
~	Z0004542	HOT-MIX ASPHALT REMOVAL (SPECIAL)	SQ YD	100	100
~	Z0004562	COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	150	150

\* - INDICATES SPECIALTY ITEMS  
~ - INDICATES SPECIAL PROVISIONS

GENERAL NOTES:

- UTILITIES INDICATED ON THE PLANS ARE PROVIDED FOR THE CONTRACTORS USE AND ARE BASED UPON INFORMATION AVAILABLE AT THE TIME OF THE ADVERTISEMENT FOR BIDS. THE OWNER AND ENGINEER DO NOT GUARANTEE THE ACCURACY OF UTILITIES INFORMATION.
- BEFORE ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 1-800-892-0123 FOR FIELD LOCATIONS OF BURIED UTILITIES. (48 HOUR NOTIFICATION IS REQUIRED)
- THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND THE VILLAGE OF WORTH.
- BARRICADES: THE CONTRACTOR SHALL PROVIDE AND INSTALL TWO (2) WEIGHTED SANDBAGS ON EACH TYPE I OR TYPE II BARRICADE. USE ONE (1) WEIGHTED SAND BAG ACROSS EACH BOTTOM RAIL.
- ALL PAVEMENT, CURB, SIDEWALK AND DRIVEWAY REMOVALS SHALL BE MADE BY MEANS OF STRAIGHT SAW CUT JOINT. THE COST FOR SAW CUTTING SHALL BE INCLUDED IN THE COST OF THE INDIVIDUAL ITEMS BEING REMOVED
- THE CONTRACTOR MAY PROSECUTE WORK BETWEEN THE HOURS OF 7:00 A.M. AND DUSK EACH WORKDAY. NO WORK WILL BE PERMITTED ON SUNDAYS, OR ON HOLIDAYS, WITHOUT PRIOR WRITTEN PERMISSION FROM THE ENGINEER.

FILE NAME = 12402-QUAN-01 - IDOT P21

USER NAME =  
PLOT SCALE = N/A  
PLOT DATE = 3-21-13

DESIGNED -- MRS  
CHECKED -- PKB  
DRAWN -- RG  
CHECKED -- AG

REVISED --  
REVISED --  
REVISED --  
REVISED --

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SIDEWALK IMPROVEMENTS  
SUMMARY OF QUANTITIES  
VILLAGE OF WORTH

SCALE: NONE

SHEET NO. 2 OF 10 SHEETS STA. TO STA.

F.A.U.  
RTE.

SECTION  
12-00062-00-SW

COUNTY

COOK

TOTAL  
SHEETS

10

SHEET  
NO.

2

CONTRACT NO. 63836

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT SRTS-4008(179)